


POOR LEGIBILITY

**PORTIONS OF THIS DOCUMENT
MAY BE UNREADABLE, DUE TO
THE QUALITY OF THE
ORIGINAL**



1927 LAKESIDE PARKWAY
SUITE 614
TUCKER, GEORGIA 30084
404-938-7710



June 6, 1990

Mr. A. R. Hanke
Site Investigation and Support Branch
Waste Management Division
Environmental Protection Agency
345 Courtland Street, N. E.
Atlanta, Georgia 30365

Date: _____
Site Disposition: _____
EPA Project Manager: _____

Subject: Screening Site Inspection Phase I
Acme Plastics, Inc.
Fort Lauderdale, Broward County, Florida
EPA ID No. FLD981026933
TDD No. F4-9002-19

Dear Mr. Hanke:

FIT 4 conducted a Screening Site Inspection of Acme Plastics, Inc. located in Fort Lauderdale, Broward County, Florida. Phase I of the inspection included a review of EPA and state file material, completion of a target survey, and a drive-by reconnaissance of the facility and surrounding area.

Acme Plastics, Inc. is located on N.W. 57th Court in Fort Lauderdale, Florida. The facility was owned and operated by Acme Plastics, Inc. from 1974 to 1982 (Ref. 1). Presently, New River Cabinet and Fixture, Inc. is at the Acme Plastics' location at the site (Ref. 2). While in operation, the facility manufactured plastic letters for the sign industry (Ref. 1).

Waste from the injection molding of plastic letters included styrene, polypropylene and acrylics, (types of plastics), hydraulic oil, and methyl ethyl ketone. Plastic scraps were either reused or baled for scrap resale. There is no information about the disposal method of either the hydraulic oil or the methyl ethyl ketone. Cooling water for the injection molding presses came from a closed-loop cooling system and involved a supply and discharge well system. In 1975, the rinsing of painted silk screens was done on the facility property. The rinsewater, paint, and cleaning fluid drained into a storm sewer (Ref. 1).

From 1974 until 1982, the Florida Department of Environmental Regulation inspected Acme Plastics, Inc. on a regular basis. In 1981, a water sample was taken at a point before it entered the discharge well. It was found to be in compliance with groundwater discharge standards (Ref. 1).

The facility area is in the Atlantic Coastal Ridge region of the Coastal Plain Physiographic Province (Ref. 3, plate-C). The area is a low, almost flat plain with low ridges near the eastern shore. There are very few natural streams, but rather a network of canals which provide drainage. The average elevation for Broward County is 2 to 10 feet above sea level. Surface soils in the area primarily consist of fine sands (Ref. 4, pp. 1, 44, 45). In southern Florida, at least one-fourth of the limestone rock is cavernous with interconnecting solution cavities, which are generally filled with sand (Ref. 5, p. 133).

Mr. A.R. Hanke
Environmental Protection Agency
TDD No. F4-9002-19
June 6, 1990 - page two

The climate is subtropical and humid with an average temperature of 75.4° F and a net annual rainfall of 13 inches (Refs. 4, pp. 1, 42; 6, pp. 43, 63). The 1-year, 24-hour rainfall is 4.5 inches (Ref. 7, p. 93).

The Biscayne Aquifer is a highly permeable, wedge-shaped, unconfined aquifer, that is about 300 feet thick in Eastern Broward County and thins to the west. The Biscayne Aquifer underlying the facility consists of the Pamlico Sand (quartz sand), Anastasia Formation (sandstone and limestone), Key Largo limestone (coralline reef rock), and the Tamiami Formation (limestones, sands, and marls). Recharge to the Biscayne Aquifer is primarily through rainfall. Downward infiltration of rain water is rapid due to sandy soils along the coast and also because of the presence of solution cavities in the limestone. The water table slopes toward the coast; however, locally the direction of flow may be influenced by drainage canals and any nearby pumping wellfields (Refs. 8, sheets 1, 2; 9, pp. 3, 15). Water table depth around the Acme Plastics' facility is about 4 feet below land surface (bls) (Ref. 10, pp. 30, 31).

Wells completed in the aquifer are drilled to depths of 40 to 100 feet bls and provide all the municipal water supplies for Broward County. The nearest municipal well is located 1 mile northeast of the facility. Transmissivity of the Biscayne Aquifer ranges from 5.0×10^5 to 2.0×10^6 ft²/day per foot, and the storage coefficient ranges from 0.047 to 0.247 (Ref. 11, pp. 3, 8). Permeability ranges from 50,000 to 70,000 gal/day/ft² (Ref. 10, p. 39). The hydraulic conductivity of the Biscayne Aquifer ranges from 1 to 1×10^{-3} cm/sec (Ref. 11, p. 29).

Below the Biscayne Aquifer is the Hawthorn Formation, a thick, confining unit consisting of sand and clay. It separates the Biscayne Aquifer from the Floridan Aquifer and is about 300 feet thick. The Floridan Aquifer System is a sequence of carbonate rock of generally high permeability that are hydraulically connected in varying degrees. It consists of an upper and a lower aquifer with a middle confining unit. The aquifer is about 1500 feet thick in this area and is unused as a drinking water source due to its high salinity (Refs. 12, pp. 4, 5; 13, pp. A7, A8).

All of the residences within 3 miles of Acme Plastics obtain water from municipal water companies (Refs. 14, 15). The Broward County Water Department serves 14,240 connections from two wellfields which consist of a total of 12 wells (Ref. 15). These wellfields are located approximately 1 mile from the Acme Plastics' facility (Ref. 14). The Fort Lauderdale Water Department serves 56,000 connections from 43 wells located approximately 3 miles from the facility (Refs. 14, 15). The residents not served by either of these water departments obtain their potable water from water departments, whose wells are located more than 4 miles from the facility. The nearest well is in the Broward County wellfield and is located approximately 4,000 feet northeast of the facility (Ref. 14). There are two water departments with wellfields located between 3 and 4 miles of Acme Plastics, Inc. (Ref. 2). The Broadview Water Department serves 2,185 connections from three wells. The Pompano Beach Water Department serves 16,900 connections from two wellfields with a total of 22 wells (Ref. 15).

Surface water runoff from the facility flows north approximately 500 feet to a large sinkhole. As this is a closed basin, the surface water pathway ends here (Ref. 14). There are several endangered and threatened species found in the state of Florida. The gopher tortoise (Gopherus polyphemus) is found in Broward County (Ref. 16).


Mr. A.R. Hanke
Environmental Protection Agency
TDD No. F4-9002-19
June 6, 1990 - page three

A facility reconnaissance was conducted at Acme Plastics, Incorporated in March 1990. The property adjacent to the facility is industrial except for a vacant lot to the south (Ref. 2). The land surrounding the facility is a mixture of residential, commercial, and industrial (Ref. 14). The nearest residence is located approximately 1,000 feet to the east (Ref. 14). The facility is not fenced and is easily accessible to the public (Ref. 2).

Based on this evaluation, no further remedial action planned is recommended for Acme Plastics, Incorporated. If you have any questions regarding this assessment, please contact me at NUS Corporation.

Very truly yours,

Approved:



Stephany Fine
Project Manager



SF/gwn

Enclosures

cc: John McKeown

REFERENCES

1. Potential Hazardous Waste Site Preliminary Assessment (EPA Form 2070-12) and attachments for Acme Plastics, Incorporated. Filed by Willard Murray, E.C. Jordan Company, November 7, 1985.
2. NUS Corporation Field Logbook No. F4-2130 for Acme Plastics, Incorporated, TDD No. F4-9002-19. Documentation of facility reconnaissance March 28, 1990.
3. William A. White, The Geomorphology of the Florida Peninsula, Geological Bulletin No. 51 (Tallahassee, Florida: Bureau of Geology, 1970).
4. U.S. Department of Agriculture, Soil Conservation Service, Soil Survey of Broward County, Florida (July 1976).
5. Gerald G. Parker et al., Water Resources of Southeastern Florida, Water-Supply Paper No. 1255 (U.S. Geological Survey, 1955).
6. U.S. Department of Commerce, Climatic Atlas of the United States (Washington, D.C.: GPO, June 1968) Reprint: 1983, National Oceanic and Atmospheric Administration.
7. U.S. Department of Commerce, Rainfall Frequency Atlas of the United States, Technical Paper No. 40 (Washington, D.C.: GPO, 1961).
8. Carmen R. Causaras, Geology of the Surficial Aquifer System, Broward County, Florida, Water Resources Investigations Report 84-4068 (U.S. Geological Survey, 1985).
9. H. Klein and J.E. Hull, Biscayne Aquifer, Southeast Florida, Water-Resources Investigations 78-107 (U.S. Geological Survey, 1978).
10. Melvin C. Schroeder, Howard Klein, and Nevin D. Hoy, Biscayne Aquifer of Dade and Broward Counties, Report of Investigations No. 17 (U.S. Geological Survey, 1958).
11. R.A. Freeze and J.A. Cherry, Groundwater (Englewood Cliffs, New Jersey: Prentice-Hall, Inc., 1979).
12. Fredrick W. Meyer, Evaluation of Hydraulic Characteristics of a Deep Artesian Aquifer from Natural Water-Level Fluctuations, I Miami, Florida, Report of Investigations No. 75 (U.S. Geological Survey, 1974).
13. Richard H. Johnston and Peter W. Bush, Summary of the Hydrology of the Floridan Aquifer System in Florida and in Parts of Georgia, South Carolina, and Alabama, Professional Paper 1403-A (U.S. Geological Survey, 1988).
14. U.S. Geological Survey, 7.5 minute series Topographic Quadrangle Maps of Florida: Boca Raton 1962 (Photorevised 1983), Fort Lauderdale North 1962 (PR 1983), Pompano Beach 1962 (PR 1983), West Dixie Bend 1962 (PR 1983), scale 1:24,000.
15. W. Smitherman, interoffice correspondence to K.D. Pass, NUS Corporation, March 22, 1990. Subject: Municipal water systems for Broward County, Florida.
16. Curtis Morgan, "Road Plan Saves Tortoise Habitat," The Miami Herald, April 26, 1990.



Site Inspection Report



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION	
01 STATE FL	02 SITE NUMBER D981026933

II. SITE NAME AND LOCATION

01 SITE NAME (Use common or descriptive name of site) Acme Plastics Inc.		02 STREET, ROUTE NO. OR SPECIFIC LOCATION IDENTIFIER 750 NW 57th Ct.				
03 CITY Fort Lauderdale		04 STATE FL	05 ZIP CODE 33309	06 COUNTY Broward	07 COUNTY CODE 011	08 COUNTY CODE 17
09 COORDINATES LATITUDE 26 12 15.00		LONGITUDE 080 23 52.00		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN		

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 11 10 81 MONTH DAY YEAR	02 SITE STATUS <input type="checkbox"/> ACTIVE <input checked="" type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1974 1982 BEGINNING YEAR ENDING YEAR		UNKNOWN	
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR <input checked="" type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR <input type="checkbox"/> G. OTHER					

05 CHIEF INSPECTOR	06 TITLE	07 ORGANIZATION	08 TELEPHONE NO.
09 OTHER INSPECTORS	10 TITLE	11 ORGANIZATION	12 TELEPHONE NO.
13 SITE REPRESENTATIVES INTERVIEWED	14 TITLE	15 ADDRESS	16 TELEPHONE NO.
17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION	19 WEATHER CONDITIONS	

IV. INFORMATION AVAILABLE FROM

01 CONTACT Eric Nuzie	02 OF Agency Organization FDER	03 TELEPHONE NO. (904) 488-0190	
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Stephany Fine	05 AGENCY	06 ORGANIZATION NV5 Corp.	07 TELEPHONE NO. (404) 938-7710
		08 DATE 4-16-90	

CERCLA ELIGIBILITY QUESTIONNAIRE

Site Name: Acme Plastics Incorporated

City: Fort Lauderdale

State: Florida

EPA I.D. Number: FLD981026933

I. CERCLA ELIGIBILITY

YES NO

Did the facility cease operations prior to November 19, 1980?

_____ ☒

If answer YES, STOP, facility is probably a CERCLA site

If answer NO, Continue to Part II

II. RCRA ELIGIBILITY

YES NO

Did the facility file a RCRA Part A application?

If YES:

- 1) Does the facility currently have interim status? _____
- 2) Did the facility withdraw its Part A application? _____
- 3) Is the facility a known or possible protective filer? (facility filed in error) _____
- 4) Type of facility:
 Generator _____ Transporter _____ Recycler _____
 TSD (Treatment/Storage/Disposal) _____

Does the facility have a RCRA operating or post closure permit?

_____ ☒

Is the facility a late (after 11/19/80) or non-filer that has been identified by the EPA or the State? (facility did not know it needed to file under RCRA)

_____ ☒

If all answers to questions in Part II are NO, STOP, the facility is a CERCLA eligible site.

If answer to #2 or #3 is YES, STOP, the facility is a CERCLA eligible site.

If #2 and #3 are NO and any OTHER answer is YES, site is RCRA, continue to Part III.

III: RCRA SITES ELIGIBLE FOR NPL

YES NO

Has the facility owner filed for bankruptcy under federal or state laws?

Has the facility lost RCRA authorization to operate or shown probable unwillingness to carry out corrective action?

Is the facility a TSD that converted to a generator, transporter or recycler facility after November 19, 1980?

RECONNAISSANCE CHECKLIST FOR HRS2 CONCERNS

Instructions: Obtain as much "up front" information as possible prior to conducting fieldwork. Complete the form in as much detail as you can, providing attachments as necessary. Cite the source for all information obtained.

Site Name: Acme Plastics, Inc.

City, County, State: Fort Lauderdale, Broward County, Florida

EPA ID No.: FLD981026933

Person responsible for form: Stephany Fine

Date: April 12, 1990

Air Pathway

Describe any potential air emission sources onsite: None

Identify any sensitive environments within 4 miles: None

Identify the maximally exposed individual (nearest residence or regularly occupied building - workers do count): Workers on site are the maximally exposed individuals.

Groundwater Pathway

Identify any areas of karst terrain: The entire 4-mile radius around the site is karst terrain.

Identify additional population due to consideration of wells completed in overlying aquifers to the AOC: None

Do significant targets exist between 3 and 4 miles from the site? No

Is the AOC a sole source aquifer according to Safe Drinking Water Act? (i.e. is the site located in Dade, Broward, Volusia, Putnam, or Flagler County, Florida): Yes, the site is located in Broward County.

Surface Water Pathway

Are there intakes located on the extended 15-mile migration pathway? No, surface water flows to a sinkhole near the site, ending the pathway.

Are there recreational areas, sensitive environments, or human food chain targets (fisheries) along the extended pathway? No

Onsite Exposure Pathway

Is there waste or contaminated soil onsite at 2 feet below land surface or higher? No

Is the site accessible to non-employees (workers do not count)? Yes, the site is not fenced.

Are there residences, schools, or day care centers onsite or in close proximity? Yes, a school is located < 1 mile from the site.

Are there barriers to travel (e.g., a river) within one mile? No

RECONNAISSANCE CHECKLIST FOR HRS2 CONCERNS

Instructions: Obtain as much "up front" information as possible prior to conducting fieldwork. Complete the form in as much detail as you can, providing attachments as necessary. Cite the source for all information obtained.

Site Name: Acme Plastics, Inc.
City, County, State: Fort Lauderdale, Broward County, Florida
EPA ID No.: FLD981026933
Person responsible for form: Stephany Fine
Date: April 12, 1990

Air Pathway

Describe any potential air emission sources onsite: None

Identify any sensitive environments within 4 miles: None

Identify the maximally exposed individual (nearest residence or regularly occupied building - workers do count): Workers on site are the maximally exposed individuals.

Groundwater Pathway

Identify any areas of karst terrain: None

Identify additional population due to consideration of wells completed in overlying aquifers to the AOC: None

Do significant targets exist between 3 and 4 miles from the site? No

Is the AOC a sole source aquifer according to Safe Drinking Water Act? (i.e. is the site located in Dade, Broward, Volusia, Putnam, or Flagler County, Florida): Yes, the site is located in Broward County.

Surface Water Pathway

Are there intakes located on the extended 15-mile migration pathway? No, surface water flows to a sinkhole near the site, ending the pathway.

Are there recreational areas, sensitive environments, or human food chain targets (fisheries) along the extended pathway? No

Onsite Exposure Pathway

Is there waste or contaminated soil onsite at 2 feet below land surface or higher? No

Is the site accessible to non-employees (workers do not count)? Yes, the site is not fenced.

Are there residences, schools, or day care centers onsite or in close proximity? Yes, a school is located < 1 mile from the site.

Are there barriers to travel (e.g., a river) within one mile? No

CERCLA ELIGIBILITY QUESTIONNAIRE

Site Name: Acme Plastics Incorporated

City: Fort Lauderdale State: Florida

EPA I.D. Number: FLD 941026933

I. CERCLA ELIGIBILITY YES NO

Did the facility cease operations prior to November 19, 1980? _____ ☒

If answer YES, STOP, facility is probably a CERCLA site
If answer NO, Continue to Part II

II. RCRA ELIGIBILITY YES NO

Did the facility file a RCRA Part A application? _____ ☒
If YES:

- 1) Does the facility currently have interim status? _____
- 2) Did the facility withdraw its Part A application? _____
- 3) Is the facility a known or possible protective filer? (facility filed in error) _____
- 4) Type of facility:
Generator _____ Transporter _____ Recycler _____
TSD (Treatment/Storage/Disposal) _____

Does the facility have a RCRA operating or post closure permit? _____ ☒

Is the facility a late (after 11/19/80) or non-filer that has been identified by the EPA or the State? (facility did not know it needed to file under RCRA) _____ ☒

If all answers to questions in Part II are NO, STOP, the facility is a CERCLA eligible site.

If answer to #2 or #3 is YES, STOP, the facility is a CERCLA eligible site.

If #2 and #3 are NO and any OTHER answer is YES, site is RCRA, continue to Part III.

III: RCRA SITES ELIGIBLE FOR NPL YES NO

Has the facility owner filed for bankruptcy under federal or state laws? _____

Has the facility lost RCRA authorization to operate or shown probable unwillingness to carry out corrective action? _____

Is the facility a TSD that converted to a generator, transporter or recycler facility after November 19, 1980? _____

HAZARD RANKING SYSTEM SCORING SUMMARY

FOR

ACME PLASTICS, INCORPORATED
EPA SITE NUMBER FLD981026933
FORT LAUDERDALE
BROWARD COUNTY, FL
EPA REGION: 4

SCORE STATUS: IN PREPARATION

SCORED BY STEPHANY FINE
OF NUS CORPORATION
ON 04/12/90

DATE OF THIS REPORT: 07/12/90
DATE OF LAST MODIFICATION: 07/12/90

GROUND WATER ROUTE SCORE : 36.53
SURFACE WATER ROUTE SCORE: 3.80
AIR ROUTE SCORE : 0.00

MIGRATION SCORE : 21.23

HRS GROUND WATER ROUTE SCORE

CATEGORY/FACTOR	RAW DATA	ASN. VALUE	SCORE
1. OBSERVED RELEASE	NO	0	0
2. ROUTE CHARACTERISTICS			
DEPTH TO WATER TABLE	4 FEET		
DEPTH TO BOTTOM OF WASTE	6 FEET		
DEPTH TO AQUIFER OF CONCERN	-2 FEET	3	6
PRECIPITATION	64.0 INCHES		
EVAPORATION	51.0 INCHES		
NET PRECIPITATION	13.0 INCHES	2	2
PERMEABILITY	1.0×10^{-2} CM/SEC	3	3
PHYSICAL STATE		3	3
TOTAL ROUTE CHARACTERISTICS SCORE:			14
3. CONTAINMENT		2	2
4. WASTE CHARACTERISTICS			
TOXICITY/PERSISTENCE:STYRENE			9
WASTE QUANTITY CUBIC YDS	2501		
DRUMS	0		
GALLONS	0		
TONS	0		
TOTAL	2501 CU. YDS	8	8
TOTAL WASTE CHARACTERISTICS SCORE:			17
5. TARGETS			
GROUND WATER USE		3	9
DISTANCE TO NEAREST WELL	4000 FEET		
AND	MATRIX VALUE	35	35
TOTAL POPULATION SERVED	256912 PERSONS		
NUMBER OF HOUSES	0		
NUMBER OF PERSONS	0		
NUMBER OF CONNECTIONS	70240		
NUMBER OF IRRIGATED ACRES	0		
TOTAL TARGETS SCORE:			44
GROUND WATER ROUTE SCORE (Sgw) = 36.53			

HRS SURFACE WATER ROUTE SCORE

CATEGORY/FACTOR	RAW DATA	ASN. VALUE	SCORE
1. OBSERVED RELEASE	NO	0	0
2. ROUTE CHARACTERISTICS			
SITE LOCATED IN SURFACE WATER	NO		
SITE WITHIN CLOSED BASIN	NO		
FACILITY SLOPE	1.0 %		
INTERVENING SLOPE	1.0 %	0	0
24-HOUR RAINFALL	4.5 INCHES	3	3
DISTANCE TO DOWN-SLOPE WATER	500 FEET	3	6
PHYSICAL STATE		3	3
TOTAL ROUTE CHARACTERISTICS SCORE:			15
3. CONTAINMENT		2	2
4. WASTE CHARACTERISTICS			
TOXICITY/PERSISTENCE: STYRENE			9
WASTE QUANTITY CUBIC YDS	2501		
DRUMS	0		
GALLONS	0		
TONS	0		
TOTAL	2501 CU. YDS	9	9
TOTAL WASTE CHARACTERISTICS SCORE:			17
5. TARGETS			
SURFACE WATER USE		2	6
DISTANCE TO SENSITIVE ENVIRONMENTS		0	0
COASTAL WETLANDS	NONE		
FRESH-WATER WETLANDS	NONE		
CRITICAL HABITAT	NONE		
DISTANCE TO STATIC WATER	500 FEET		
DISTANCE TO WATER SUPPLY INTAKE	0 FEET		
AND MATRIX VALUE		0	0
TOTAL POPULATION SERVED	0		
NUMBER OF HOUSES	0		
NUMBER OF PERSONS	0		
NUMBER OF CONNECTIONS	0		
NUMBER OF IRRIGATED ACRES	0		
TOTAL TARGETS SCORE:			6
SURFACE WATER ROUTE SCORE (SWR) = 3.50			

HRS AIR ROUTE SCORE

<u>CATEGORY/FACTOR</u>	<u>RAW DATA</u>	<u>ASN. VALUE</u>	<u>SCORE</u>
1. OBSERVED RELEASE	NO	0	0
<hr/>			
2. WASTE CHARACTERISTICS			
REACTIVITY:			
INCOMPATIBILITY		MATRIX VALUE	
TOXICITY			
WASTE QUANTITY	CUBIC YARDS		
	DRUMS		
	GALLONS		
	TONS		
	TOTAL		
TOTAL WASTE CHARACTERISTICS SCORE:			N/A
<hr/>			
3. TARGETS			
POPULATION WITHIN 4-MILE RADIUS			
0 to 0.25 mile			
0 to 0.50 mile			
0 to 1.0 mile			
0 to 4.0 miles			
DISTANCE TO SENSITIVE ENVIRONMENTS			
COASTAL WETLANDS			
FRESH-WATER WETLANDS			
CRITICAL HABITAT			
DISTANCE TO LAND USES			
COMMERCIAL/INDUSTRIAL			
PARK/FOREST/RESIDENTIAL			
AGRICULTURAL LAND			
PRIME FARMLAND			
HISTORIC SITE WITHIN VIEW?			
TOTAL TARGETS SCORE:			N/A

AIR ROUTE SCORE (Sa) = 0.00

HAZARD RANKING SYSTEM SCORING CALCULATIONS
FOR
SITE: ACME PLASTICS, INCORPORATED
AS OF 07/12/90

PAGE 5

GROUND WATER ROUTE SCORE

ROUTE CHARACTERISTICS		14
CONTAINMENT	X	2
WASTE CHARACTERISTICS	X	17
TARGETS	X	44

$$= 20944 / 57,330 \times 100 = 36.53 = S_{gw}$$

SURFACE WATER ROUTE SCORE

ROUTE CHARACTERISTICS		12
CONTAINMENT	X	2
WASTE CHARACTERISTICS	X	17
TARGETS	X	6

$$= 2448 / 64,350 \times 100 = 3.80 = S_{sw}$$

AIR ROUTE SCORE

$$\text{OBSERVED RELEASE} \quad 0 / 35,100 \times 100 = 0.00 = S_{air}$$

SUMMARY OF MIGRATION SCORE CALCULATIONS

	<u>S</u>	<u>S²</u>
GROUND WATER ROUTE SCORE (S _{gw})	36.53	1334.44
SURFACE WATER ROUTE SCORE (S _{sw})	3.80	14.44
AIR ROUTE SCORE (S _{air})	0.00	0.00
S ² _{gw} + S ² _{sw} + S ² _{air}		1348.88
√ (S ² _{gw} + S ² _{sw} + S ² _{air})		36.73
S _M = √ (S ² _{gw} + S ² _{sw} + S ² _{air}) / 1.73		21.23



Site Inspection Report



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION	
01 STATE FL	02 SITE NUMBER D981026933

II. SITE NAME AND LOCATION


01 SITE NAME (Legal, common, or descriptive name of site) Acme Plastics Inc.		02 STREET, ROUTE NO. OR SPECIFIC LOCATION IDENTIFIER 750 NW 57th Ct.				
03 CITY Fort Lauderdale		04 STATE FL	05 ZIP CODE 33309	06 COUNTY Broward	07 COUNTY CODE 011	08 COUNTY DIST. 17
09 COORDINATES LATITUDE 26 12 15. _ LONGITUDE 080 08 57. _		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN				

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 11 10 81 MONTH DAY YEAR		02 SITE STATUS <input type="checkbox"/> ACTIVE <input checked="" type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1974 1982 BEGINNING YEAR ENDING YEAR		UNKNOWN	
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR <input checked="" type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR <input type="checkbox"/> G. OTHER						
05 CHIEF INSPECTOR		06 TITLE		07 ORGANIZATION	08 TELEPHONE NO ()	
09 OTHER INSPECTORS		10 TITLE		11 ORGANIZATION	12 TELEPHONE NO ()	
					()	
					()	
					()	
					()	
					()	
13 SITE REPRESENTATIVES INTERVIEWED		14 TITLE	15 ADDRESS		16 TELEPHONE NO ()	
					()	
					()	
					()	
					()	
					()	
					()	
					()	
					()	
17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT		18 TIME OF INSPECTION		19 WEATHER CONDITIONS		

IV. INFORMATION AVAILABLE FROM

01 CONTACT Eric Nuzie		02 OF (Agency, Organization) FDER		03 TELEPHONE NO (904) 488-0190	
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Stephany Fine		05 AGENCY	06 ORGANIZATION NVS Corp.	07 TELEPHONE NO. (404) 938-7710	08 DATE 4-16-90 MONTH DAY YEAR



03 WASTE CHARACTERISTICS (Check all that apply)

<input checked="" type="checkbox"/> A TOXIC	<input type="checkbox"/> E SOLUBLE	<input type="checkbox"/> I HIGHLY VOLATILE
<input type="checkbox"/> B CORROSIVE	<input type="checkbox"/> F INFECTIOUS	<input type="checkbox"/> J EXPLOSIVE
<input type="checkbox"/> C RADIOACTIVE	<input type="checkbox"/> G FLAMMABLE	<input type="checkbox"/> K REACTIVE
<input type="checkbox"/> D PERSISTENT	<input type="checkbox"/> H IGNITABLE	<input type="checkbox"/> L INCOMPATIBLE
		<input type="checkbox"/> M NOT APPLICABLE

IV. HAZARDOUS SUBSTANCES See Appendix for most frequently cited CAS Numbers.

V. FEEDSTOCKS See 4609214 for CAS Numbers)VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, records)

EPA FORM 2070-13(7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL 0961026933

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

Rinsewater drained to storm sewer + could contaminate the groundwater

01 ☒ B SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

Groundwater contaminants could enter surface water

01 ☐ C CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Possible if soil is contaminated, but unknown

01 ☒ D FIRE EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

The solvents used are flammable

01 ☒ E DIRECT CONTACT 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

At the present time, the site does not restrict access

01 ☒ F CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: < 0.5 04 NARRATIVE DESCRIPTION

Possible spills or discharge of rinsewater could contaminate soil on site

01 ☒ G DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

Site is near Fort Lauderdale municipal wellfield

01 ☐ H WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

The Acme facility is no longer active, so workers won't be exposed.

01 ☒ I POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

Resident of the area may be exposed through groundwater and drinking water



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL D991026933

II. HAZARDOUS CONDITIONS AND INCIDENTS (continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

No signs of stressed vegetation

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include names of species)

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

None known

01 ☒ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☒ POTENTIAL

☐ ALLEGED

Through fishing in contaminated surface water

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES

(Spills, Runoff, Standing liquids, Leaking drums)

02 ☐ OBSERVED (DATE _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 10,000+

04 NARRATIVE DESCRIPTION

Containment of oil + MEK is unknown

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

None known

01 ☒ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs

02 ☐ OBSERVED (DATE _____)

☒ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

Contaminated rinsewater washed into storm sewer

01 ☐ P. ILLEGAL UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

None known

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

None

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, etc.):

EPA + State Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE **FL** 02 SITE NUMBER **0961026933**

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED <small>Check all that apply</small>	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A NPDES				
<input type="checkbox"/> B UIC				
<input type="checkbox"/> C AIR				
<input type="checkbox"/> D RCRA				
<input type="checkbox"/> E RCRA INTERIM STATUS				
<input type="checkbox"/> F SPCC PLAN				
<input type="checkbox"/> G STATE <small>Specify</small>				
<input type="checkbox"/> H LOCAL <small>Specify</small>				
<input type="checkbox"/> I OTHER <small>Specify</small>				
<input type="checkbox"/> J NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL <small>Check all that apply</small>	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT <small>Check all that apply</small>	05 OTHER
<input type="checkbox"/> A SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input checked="" type="checkbox"/> C. DRUMS, ABOVE GROUND	<u>Unknown</u>		<input type="checkbox"/> C. CHEMICAL PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input checked="" type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER <small>Specify</small>	
<input type="checkbox"/> I. OTHER <small>Specify</small>				06 AREA OF SITE <u>0.5</u> acres

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES Check one

☐ A. ADEQUATE, SECURE ☒ B. MODERATE ☐ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE ☒ YES ☐ NO

02 COMMENTS Site is not fenced & access is not restricted

VI. SOURCES OF INFORMATION Cite specific references, e.g. state files, same analysis reports

EPA & State Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

FL D961026933

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY
(Check as applicable)

SURFACE WELL
COMMUNITY A ☐ B ☒
NON-COMMUNITY C ☐ D ☐

02 STATUS

ENDANGERED A ☒ D ☐
AFFECTED B ☐ E ☐
MONITORED C ☐ F ☐

03 DISTANCE TO SITE

A < 1 (mi)
B _____ (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A ONLY SOURCE FOR DRINKING
☐ B DRINKING
Other sources available:
COMMERCIAL, INDUSTRIAL, IRRIGATION
No other water sources available
☐ C COMMERCIAL, INDUSTRIAL, IRRIGATION
Limited other sources available
☐ D NOT USED UNUSEABLE

02 POPULATION SERVED BY GROUND WATER 10,000+

03 DISTANCE TO NEAREST DRINKING WATER WELL < 1 (mi)

04 DEPTH TO GROUNDWATER

4 (ft)

05 DIRECTION OF GROUNDWATER FLOW

N

06 DEPTH TO AQUIFER
OF CONCERN

4 (ft)

07 POTENTIAL YIELD
OF AQUIFER

60,000 (gpd)

08 SOLE SOURCE AQUIFER

☒ YES ☐ NO

09 DESCRIPTION OF WELLS (including usage, depth, and location relative to population and buildings)

Municipal wells < 1 mile from facility

10 RECHARGE AREA

☒ YES
☐ NO

COMMENTS Through rainwater

11 DISCHARGE AREA

☐ YES
☐ NO

COMMENTS

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A RESERVOIR, RECREATION
DRINKING WATER SOURCE
☐ B IRRIGATION, ECONOMICALLY
IMPORTANT RESOURCES
☐ C COMMERCIAL, INDUSTRIAL
☐ D NOT CURRENTLY USED

02 AFFECTED POTENTIALLY AFFECTED BODIES OF WATER

NAME

AFFECTED

DISTANCE TO SITE

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE

TWO (2) MILES OF SITE

THREE (3) MILES OF SITE

A _____
NO. OF PERSONS

B _____
NO. OF PERSONS

C _____
NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

_____ (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

04 DISTANCE TO NEAREST OFF-SITE BUILDING

< 1 (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., total village, densely populated urban area)

Urban densely-populated



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL 0991026933

VI. ENVIRONMENTAL INFORMATION

03 PERMEABILITY OF UNSATURATED ZONE (check one)

A $10^{-9} - 10^{-8}$ cm/sec B $10^{-8} - 10^{-6}$ cm/sec C $10^{-6} - 10^{-3}$ cm/sec ☒ D GREATER THAN 10^{-3} cm/sec

04 PERMEABILITY OF BEDROCK (check one)

A IMPERMEABLE (Less than 10^{-9} cm/sec) B RELATIVELY IMPERMEABLE ($10^{-9} - 10^{-5}$ cm/sec) C RELATIVELY PERMEABLE ($10^{-5} - 10^{-2}$ cm/sec) ☒ D VERY PERMEABLE (Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

_____ (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

_____ (ft)

05 SOIL pH

06 NET PRECIPITATION

13 (in)

07 ONE YEAR 24 HOUR RAINFALL

4.5 (in)

08 SLOPE
SITE SLOPE

1 %

DIRECTION OF SITE SLOPE

N

TERRAIN AVERAGE SLOPE

1 %

09 FLOOD POTENTIAL

SITE IS IN _____ YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A > 3 (mi)

B > 3 (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

> 3 (mi)

ENDANGERED SPECIES: _____

13 LAND USE IN VICINITY

DISTANCE TO

COMMERCIAL INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A < 1 (mi)

B > 3 (mi)

C > 3 (mi) D > 3 (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Site is located in a higher land area south
of a large sinkhole.

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis reports)

EPA & State Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL DA61026933

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPIII			
SOIL			
VEGETATION			
OTHER Discharge well			1982

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF _____ <small>Name of organization or individual</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS NVS Corp

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

Results of water samples at discharge well show facility to be in compliance with groundwater standards

VI. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis reports)

EPA & State Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL 0981026933

II. CURRENT OWNER(S)				PARENT COMPANY (If applicable)			
01 NAME New River Cabinet		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 750 NW 57th Ct		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY Fort Lauderdale		06 STATE FL	07 ZIP CODE 33309	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (List most recent first)				IV. REALTY OWNER(S) (If applicable, list most recent first)			
01 NAME Foam Factory		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 750 NW 57th Ct.		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY Fort Lauderdale		06 STATE FL	07 ZIP CODE 33309	05 CITY		06 STATE	07 ZIP CODE
01 NAME Acme Plastics		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 750 NW 57th Ct		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY Fort Lauderdale		06 STATE FL	07 ZIP CODE 33309	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
V. SOURCES OF INFORMATION (Cite specific references, e.g. State files, sample analysis reports.)							
EPA & State Files, Recon							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL 0981026933

II. CURRENT OPERATOR <small>(Provide if different from owner)</small>				OPERATOR'S PARENT COMPANY <small>(If applicable)</small>			
01 NAME <i>New River Cabinet</i>		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) <small>(List most recent first, provide only if different from owner)</small>				PREVIOUS OPERATORS' PARENT COMPANIES <small>(If applicable)</small>			
01 NAME <i>Foam Factory</i>		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME <i>Acme Plastics</i>		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, RFD #, etc.)</small>		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis, etc.)

EPA + State Files, Recon



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL D991026933

II. ON-SITE GENERATOR

01 NAME None	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME Unknown	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

V. SOURCES OF INFORMATION (cite specific references, e.g., state files, sample analysis reports)

EPA & State Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL 0981026933

II. PAST RESPONSE ACTIVITIES

01 ☐ A WATER SUPPLY CLOSED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ B TEMPORARY WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ C PERMANENT WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ D SPILLED MATERIAL REMOVED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ E CONTAMINATED SOIL REMOVED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ F WASTE REPACKAGED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ G WASTE DISPOSED ELSEWHERE
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ H ON SITE BURIAL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ I IN SITU CHEMICAL TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ J IN SITU BIOLOGICAL TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ K IN SITU PHYSICAL TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ L ENCAPSULATION
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ M EMERGENCY WASTE TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ N CUTOFF WALLS
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ O EMERGENCY Diking SURFACE WATER DIVERSION
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ P CUTOFF TRENCHES/SUMP
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None

01 ☐ Q SUBSURFACE CUTOFF WALL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

None



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL 0981026933

II. PAST RESPONSE ACTIVITIES (Continued)

01 <input type="checkbox"/> R BARRIER WALLS CONSTRUCTED 04 DESCRIPTION <i>None</i>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> S CAPPING COVERING 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> T BULK TANKAGE REPAIRED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> U GROUT CURTAIN CONSTRUCTED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> V BOTTOM SEALED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> W GAS CONTROL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> X FIRE CONTROL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Y LEACHATE TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Z AREA EVACUATED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 1 ACCESS TO SITE RESTRICTED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 2 POPULATION RELOCATED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 3 OTHER REMEDIAL ACTIVITIES 04 DESCRIPTION	02 DATE _____	03 AGENCY _____

III. SOURCES OF INFORMATION Cite specific references, e.g. state files, sample analysis reports.

EPA & State Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
FL	0981026933

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY ENFORCEMENT ACTION ☐ YES ☒ NO

02 DESCRIPTION OF FEDERAL / STATE / LOCAL REGULATORY ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis reports)

EPA & State Files

APPENDIX

I. FEEDSTOCKS

CAS Number	Chemical Name	CAS Number	Chemical Name	CAS Number	Chemical Name
1. 7664-41-7	Ammonia	14. 1317-38-0	Cupric Oxide	27. 7778-50-9	Potassium Dichromate
2. 7440-36-0	Antimony	15. 7758-98-7	Cupric Sulfate	28. 1310-58-3	Potassium Hydroxide
3. 1309-64-4	Antimony Trioxide	16. 1317-39-1	Cuprous Oxide	29. 115-07-1	Propylene
4. 7440-38-2	Arsenic	17. 74-85-1	Ethylene	30. 10588-01-9	Sodium Dichromate
5. 1327-53-3	Arsenic Trioxide	18. 7647-01-0	Hydrochloric Acid	31. 1310-73-2	Sodium Hydroxide
6. 21109-95-5	Barium Sulfide	19. 7664-39-3	Hydrogen Fluoride	32. 7646-78-8	Stannic Chloride
7. 7726-95-6	Bromine	20. 1335-25-7	Lead Oxide	33. 7772-99-8	Stannous Chloride
8. 106-99-0	Butadiene	21. 7439-97-6	Mercury	34. 7664-93-9	Sulfuric Acid
9. 7440-43-9	Cadmium	22. 74-82-8	Methane	35. 108-88-3	Toluene
10. 7782-50-5	Chlorine	23. 91-20-3	Napthalene	36. 1330-20-7	Xylene
11. 12737-27-8	Chromite	24. 7440-02-0	Nickel	37. 7646-85-7	Zinc Chloride
12. 7440-47-3	Chromium	25. 7697-37-2	Nitric Acid	38. 7733-02-0	Zinc Sulfate
13. 7440-48-4	Cobalt	26. 7723-14-0	Phosphorus		

II. HAZARDOUS SUBSTANCES

CAS Number	Chemical Name	CAS Number	Chemical Name	CAS Number	Chemical Name
1. 75-07-0	Acetaldehyde	47. 1303-33-9	Arsenic Trisulfide	92. 142-71-2	Cupric Acetate
2. 64-19-7	Acetic Acid	48. 542-62-1	Barium Cyanide	93. 12002-03-8	Cupric Acetoarsenite
3. 108-24-7	Acetic Anhydride	49. 71-43-2	Benzene	94. 7447-39-4	Cupric Chloride
4. 75-86-5	Acetone Cyanohydrin	50. 65-85-0	Benzoic Acid	95. 3251-23-8	Cupric Nitrate
5. 506-96-7	Acetyl Bromide	51. 100-47-0	Benzonitrile	96. 5893-66-3	Cupric Oxalate
6. 75-36-5	Acetyl Chloride	52. 98-88-4	Benzoyl Chloride	97. 7758-98-7	Cupric Sulfate
7. 107-02-8	Acrolein	53. 100-44-7	Benzyl Chloride	98. 10380-29-7	Cupric Sulfate Ammoniated
8. 107-13-1	Acrylonitrile	54. 7440-41-7	Beryllium	99. 815-82-7	Cupric Tartrate
9. 124-04-9	Adipic Acid	55. 7787-47-5	Beryllium Chloride	100. 506-77-4	Cyanogen Chloride
10. 309-00-2	Aldrin	56. 7787-49-7	Beryllium Fluoride	101. 110-82-7	Cyclohexane
11. 10043-01-3	Aluminum Sulfate	57. 13597-99-4	Beryllium Nitrate	102. 94-75-7	2,4-D Acid
12. 107-18-6	Allyl Alcohol	58. 123-86-4	Butyl Acetate	103. 94-11-1	2,4-D Esters
13. 107-05-1	Allyl Chloride	59. 84-74-2	n-Butyl Phthalate	104. 50-29-3	DDT
14. 7664-41-7	Ammonia	60. 109-73-9	Butylamine	105. 333-41-5	Diazinon
15. 631-61-8	Ammonium Acetate	61. 107-92-6	Butyric Acid	106. 1918-00-9	Dicamba
16. 1863-63-4	Ammonium Benzoate	62. 543-90-8	Cadmium Acetate	107. 1194-65-6	Dichlobenil
17. 1066-33-7	Ammonium Bicarbonate	63. 7789-42-6	Cadmium Bromide	108. 117-80-6	Dichlone
18. 7789-09-5	Ammonium Bichromate	64. 10108-64-2	Cadmium Chloride	109. 25321-22-6	Dichlorobenzene (all isomers)
19. 1341-49-7	Ammonium Bifluoride	65. 7778-44-1	Calcium Arsenate	110. 266-38-19-7	Dichloropropane (all isomers)
20. 10192-30-0	Ammonium Bisulfite	66. 52740-16-6	Calcium Arsenite	111. 26952-23-8	Dichloropropene (all isomers)
21. 1111-78-0	Ammonium Carbamate	67. 75-20-7	Calcium Carbide	112. 8003-19-8	Dichloropropene-Dichloropropane Mixture
22. 12125-02-9	Ammonium Chloride	68. 13765-19-0	Calcium Chromate	113. 75-99-0	2,2-Dichloropropionic Acid
23. 7788-98-9	Ammonium Chromate	69. 592-01-8	Calcium Cyanide	114. 62-73-7	Dichlorvos
24. 3012-65-5	Ammonium Citrate, Dibasic	70. 26264-06-2	Calcium Dodecylbenzene Sulfonate	115. 60-57-1	Dieldrin
25. 13826-83-0	Ammonium Fluoborate	71. 7778-54-3	Calcium Hypochlorite	116. 109-89-7	Diethylamine
26. 12125-01-8	Ammonium Fluoride	72. 133-06-2	Captan	117. 124-40-3	Dimethylamine
27. 1336-21-6	Ammonium Hydroxide	73. 63-25-2	Carbaryl	118. 25154-54-5	Dinitrobenzene (all isomers)
28. 6009-70-7	Ammonium Oxalate	74. 1563-66-2	Carbofuran	119. 51-28-5	Dinitrophenol
29. 16919-19-0	Ammonium Silicofluoride	75. 75-15-0	Carbon Disulfide	120. 25321-14-6	Dinitrotoluene (all isomers)
30. 7773-06-0	Ammonium Sulfamate	76. 56-23-5	Carbon Tetrachloride	121. 85-00-7	Diquat
31. 12135-76-1	Ammonium Sulfide	77. 57-74-9	Chlordane	122. 298-04-4	Disulfoton
32. 10196-04-0	Ammonium Sulfite	78. 7782-50-5	Chlorine	123. 330-54-1	Diuron
33. 14307-43-8	Ammonium Tartrate	79. 108-90-7	Chlorobenzene	124. 27176-87-0	Dodecylbenzenesulfonic Acid
34. 1762-95-4	Ammonium Thiocyanate	80. 67-66-3	Chloroform	125. 115-29-7	Endosulfan (all isomers)
35. 7783-18-8	Ammonium Thiosulfate	81. 7790-94-5	Chlorosulfonic Acid	126. 72-20-8	Endrin and Metabolites
36. 628-63-7	Amyl Acetate	82. 2921-88-2	Chlorpyrifos	127. 106-89-8	Epichlorohydrin
37. 62-53-3	Aniline	83. 1066-30-4	Chromic Acetate	128. 563-12-2	Ethion
38. 7647-18-9	Antimony Pentachloride	84. 7738-94-5	Chromic Acid	129. 100-41-4	Ethyl Benzene
39. 7789-61-9	Antimony Tribromide	85. 10101-53-8	Chromic Sulfate	130. 107-15-3	Ethylenediamine
40. 10025-91-9	Antimony Trichloride	86. 10049-05-5	Chromous Chloride	131. 106-93-4	Ethylene Dibromide
41. 7783-56-4	Antimony Trifluoride	87. 544-18-3	Cobaltous Formate	132. 107-06-2	Ethylene Dichloride
42. 1309-64-4	Antimony Trioxide	88. 14017-41-5	Cobaltous Sulfamate	133. 60-00-4	EDTA
43. 1303-32-8	Arsenic Disulfide	89. 56-72-4	Coumaphos	134. 1185-57-5	Ferric Ammonium Citrate
44. 1303-28-2	Arsenic Pentoxide	90. 1319-77-3	Cresol	135. 2944-67-4	Ferric Ammonium Oxalate
45. 7784-34-1	Arsenic Trichloride	91. 4170-30-3	Crotonaldehyde	136. 7705-08-0	Ferric Chloride
46. 1327-53-3	Arsenic Trioxide				

II. HAZARDOUS SUBSTANCES

CAS Number	Chemical Name	CAS Number	Chemical Name	CAS Number	Chemical Name
137. 7783-50-8	Ferric Fluoride	192. 74-89-5	Monomethylamine	249. 7632-00-0	Sodium Nitrate
138. 10421-48-4	Ferric Nitrate	193. 300-76-5	Naled	250. 7558-79-4	Sodium Phosphate, Dibasic
139. 10028-22-5	Ferric Sulfate	194. 91-20-3	Naphthalene	251. 7601-54-9	Sodium Phosphate, Tri basic
140. 10045-89-3	Ferrous Ammonium Sulfate	195. 1338-24-5	Naphthenic Acid	252. 10102-18-8	Sodium Selenite
141. 7758-94-3	Ferrous Chloride	196. 7440-02-0	Nickel	253. 7789-06-2	Strontium Chromate
142. 7720-78-7	Ferrous Sulfate	197. 15699-18-0	Nickel Ammonium Sulfate	254. 57-24-9	Strychnine and Salts
143. 206-44-0	Fluoranthene	198. 37211-05-5	Nickel Chloride	255. 100-420-5	Styrene
144. 50-00-0	Formaldehyde	199. 12054-48-7	Nickel Hydroxide	256. 12771-08-3	Sulfur Monochloride
145. 64-18-6	Formic Acid	200. 14216-75-2	Nickel Nitrate	257. 7664-93-9	Sulfuric Acid
146. 110-17-8	Fumaric Acid	201. 7786-81-4	Nickel Sulfate	258. 93-76-5	2,4,5-T Acid
147. 98-01-1	Furfural	202. 7697-37-2	Nitric Acid	259. 2008-46-0	2,4,5-T Amines
148. 86-50-0	Guthion	203. 98-95-3	Nitrobenzene	260. 93-79-8	2,4,5-T Esters
149. 76-44-8	Heptachlor	204. 10102-44-0	Nitrogen Dioxide	261. 13560-99-1	2,4,5-T Salts
150. 118-74-1	Hexachlorobenzene	205. 25154-55-6	Nitrophenol (all isomers)	262. 93-72-1	2,4,5-TP Acid
151. 87-68-3	Hexachlorobutadiene	206. 1321-12-6	Nitrotoluene	263. 32534-95-5	2,4,5-TP Acid Esters
152. 67-72-1	Hexachloroethane	207. 30525-89-4	Paraformaldehyde	264. 72-54-8	TDE
153. 70-30-4	Hexachlorophene	208. 56-38-2	Parathion	265. 95-94-3	Tetrachlorobenzene
154. 77-47-4	Hexachlorocyclopentadiene	209. 608-93-5	Pentachlorobenzene	266. 127-18-4	Tetrachloroethane
155. 7647-01-0	Hydrochloric Acid (Hydrogen Chloride)	210. 87-86-5	Pentachlorophenol	267. 78-00-2	Tetraethyl Lead
156. 7664-39-3	Hydrofluoric Acid (Hydrogen Fluoride)	211. 85-01-8	Phenanthrene	268. 107-49-3	Tetraethyl Pyrophosphate
157. 74-90-8	Hydrogen Cyanide	212. 108-95-2	Phenol	269. 7446-18-6	Thallium (I) Sulfate
158. 7783-06-4	Hydrogen Sulfide	213. 75-44-5	Phosgene	270. 108-88-3	Toluene
159. 78-79-5	Isoprene	214. 7664-38-2	Phosphoric Acid	271. 8001-35-2	Toxaphene
160. 42504-46-1	Isopropanolamine Dodecylbenzenesulfonate	215. 7723-14-0	Phosphorus	272. 12002-48-1	Trichlorobenzene (all isomers)
161. 115-32-2	Kelthane	216. 10025-87-3	Phosphorus Oxychloride	273. 52-68-6	Trichlorfon
162. 143-50-0	Kepone	217. 1314-80-3	Phosphorus Pentasulfide	274. 25323-89-1	Trichloroethane (all isomers)
163. 301-04-2	Lead Acetate	218. 7719-12-2	Phosphorus Trichloride	275. 79-01-6	Trichloroethylene
164. 3687-31-8	Lead Arsenate	219. 7784-41-0	Potassium Arsenate	276. 25167-82-2	Trichlorophenol (all isomers)
165. 7758-95-4	Lead Chloride	220. 10124-50-2	Potassium Arsenite	277. 27323-41-7	Triethanolamine Dodecylbenzenesulfonate
166. 13814-96-5	Lead Fluoborate	221. 7778-50-9	Potassium Bichromate	278. 121-44-8	Triethylamine
167. 7783-46-2	Lead Fluoride	222. 7789-00-6	Potassium Chromate	279. 75-50-3	Trimethylamine
168. 10101-63-0	Lead Iodide	223. 7722-64-7	Potassium Permanganate	280. 541-09-3	Uranyl Acetate
169. 18256-98-9	Lead Nitrate	224. 2312-35-8	Propargite	281. 10102-06-4	Uranyl Nitrate
170. 7428-48-0	Lead Stearate	225. 79-09-4	Propionic Acid	282. 1314-62-1	Vanadium Pentoxide
171. 15739-80-7	Lead Sulfate	226. 123-62-6	Propionic Anhydride	283. 27774-13-6	Vanadyl Sulfate
172. 1314-87-0	Lead Sulfide	227. 1336-36-3	Polychlorinated Biphenyls	284. 108-05-4	Vinyl Acetate
173. 592-87-0	Lead Thiocyanate	228. 151-50-8	Potassium Cyanide	285. 75-35-4	Vinylidene Chloride
174. 58-89-9	Lindane	229. 1310-58-3	Potassium Hydroxide	286. 1300-71-6	Xylenol
175. 14307-35-8	Lithium Chromate	230. 75-56-9	Propylene Oxide	287. 557-34-6	Zinc Acetate
176. 121-75-5	Malthion	231. 121-29-9	Pyrethrins	288. 52628-25-8	Zinc Ammonium Chloride
177. 110-16-7	Maleic Acid	232. 91-22-5	Quinoline	289. 1332-07-6	Zinc Borate
178. 108-31-6	Maleic Anhydride	233. 108-46-3	Resorcinol	290. 7699-45-8	Zinc Bromide
179. 2032-65-7	Mercaptodimethur	234. 7446-08-4	Selenium Oxide	291. 3486-35-9	Zinc Carbonate
180. 592-04-1	Mercuric Cyanide	235. 7761-88-8	Silver Nitrate	292. 7646-85-7	Zinc Chloride
181. 10045-94-0	Mercuric Nitrate	236. 7631-89-2	Sodium Arsenate	293. 557-21-1	Zinc Cyanide
182. 7783-35-9	Mercuric Sulfate	237. 7784-46-5	Sodium Arsenite	294. 7783-49-3	Zinc Fluoride
183. 592-85-8	Mercuric Thiocyanate	238. 10588-01-9	Sodium Bichromate	295. 557-41-5	Zinc Formate
184. 10415-75-5	Mercurous Nitrate	239. 1333-83-1	Sodium Bifluoride	296. 7779-86-4	Zinc Hydrosulfite
185. 72-43-5	Methoxychlor	240. 7631-90-5	Sodium Bisulfite	297. 7779-88-6	Zinc Nitrate
186. 74-93-1	Methyl Mercaptan	241. 7775-11-3	Sodium Chromate	298. 127-82-2	Zinc Phenolsulfonate
187. 80-62-6	Methyl Methacrylate	242. 143-33-9	Sodium Cyanide	299. 1314-84-7	Zinc Phosphide
188. 298-00-0	Methyl Parathion	243. 25155-30-0	Sodium Dodecylbenzene Sulfonate	300. 16871-71-9	Zinc Silicofluoride
189. 7786-34-7	Mevinphos	244. 7681-49-4	Sodium Fluoride	301. 7733-02-0	Zinc Sulfate
190. 315-18-4	Mexacarbate	245. 16721-80-5	Sodium Hydrosulfide	302. 13746-89-9	Zirconium Nitrate
191. 75-04-7	Monoethylamine	246. 1310-73-2	Sodium Hydroxide	303. 16923-95-8	Zirconium Potassium Fluoride
		247. 7681-52-9	Sodium Hypochlorite	304. 14644-61-2	Zirconium Sulfate
		248. 124-41-4	Sodium Methylate	305. 10026-11-6	Zirconium Tetrachloride

Reference 1

ACME PLASTICS, INC.
FLD981026933
PRELIMINARY ASSESSMENT

J.L.E.W.

- A. SITE DESCRIPTION. Acme Plastics, Inc. was located in a commercial/ industrial area at 750 NW 57th CT, Fort Lauderdale, Broward County, Florida. The facility was a manufacturer of plastic letters for the sign industry from at least 1974 to 1982. The Foam Factory is now located at this site.
- B. DESCRIPTION OF HAZARDOUS CONDITIONS, INCIDENTS AND PERMIT VIOLATIONS. Acme Plastics, Inc. was a manufacturer of plastic letters for signs and the process involved injection molding. The plastics that were used were styrene, polypropylene and acrylics. Waste plastic was reused or baled for scrap resale. The injection molding presses required cooling water and hydraulic oil. Methyl ethyl ketone (MEK) was used during the manufacturing of the plastic until 1979. An industrial sludge survey, 5/19/81, stated that no waste is generated, and as of 3/18/82, the facility was given a non-source status. The Foam Factory is now located at this site, and there is no information available about this facility.
- Cooling water for the injection molding presses was obtained from a closed loop supply and discharge well system. Both supply and discharge wells are 4 inches in diameter and 150 feet deep, with a maximum continuous flow of 10,000 GPD. On 11/10/81 water samples were taken from the system just before the discharge well. The results indicated that the facility was in compliance with groundwater discharge standards. The current status of the supply/discharge wells is unknown. No permit violations have been reported.
- C. NATURE OF HAZARDOUS MATERIALS. The hazardous materials that were at the site were MEK which is volatile, reactive and flammable, styrene which is reactive and flammable, paint and oil.
- D. ROUTES OF CONTAMINATION. Possible routes of contamination include drinking water, surface water, soils and groundwater used for irrigation and other purposes.
- E. POSSIBLE AFFECTED POPULATION AND RESOURCES. Area residents are provided with drinking water from the City of Fort Lauderdale Executive/ Prospect municipal wellfield. The wellfield draws from the Biscayne aquifer, which is a shallow, permeable, sole-source aquifer. The site is located 2000 feet east of the nearest wells, thus, potential contaminants in the groundwater may reach the wellfield.
- F. RECOMMENDATIONS AND JUSTIFICATIONS. Acme Plastics, Inc. is no longer located at this site; the present site occupant is the Foam Factory. Acme Plastics was given a "non-source status" in March, 1982. There is no information available for the Foam Factory. A low priority for inspection is recommended at this facility; however, the status of the well system should be ascertained.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL D9810269

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) Acme Plastics, Inc.		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 750 NW 57th CT			
03 CITY Fort Lauderdale	04 STATE FL	05 ZIP CODE 33309	06 COUNTY Broward	07 COUNTY CODE 011	08 CENSUS DIST 17
09 COORDINATES LATITUDE 26 12 15		LONGITUDE 08 08 57			
10 DIRECTIONS TO SITE (Starting from nearest public road) Proceed north on I-95 from Fort Lauderdale, exit onto Commercial Blvd; proceed west on Commercial Blvd. 1/4 mile to Powerline Rd.; proceed north on Powerline 3000 feet to NW 57th CT.; proceed east on NW 57th CT, the site is the last building on the left.					

III. RESPONSIBLE PARTIES

01 OWNER (if known) Acme Plastics, Inc.		02 STREET (Business, mailing, residential) 750 NW 57th CT			
03 CITY Fort Lauderdale	04 STATE FL	05 ZIP CODE 33309	06 TELEPHONE NUMBER (305) 772-3720		
07 OPERATOR (if known and different from owner) Frank Nickola - General Manager		08 STREET (Business, mailing, residential) Same			
09 CITY Fort Lauderdale	10 STATE FL	11 ZIP CODE 33309	12 TELEPHONE NUMBER ()		

13 TYPE OF OWNERSHIP (Check one)
☒ A. PRIVATE ☐ B. FEDERAL: _____ (Agency name)
☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL
☐ F. OTHER: _____ (Specify)
☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)
☐ A. RCRA 3001 DATE RECEIVED: _____ MONTH DAY YEAR
☐ B. UNCONTROLLED WASTE SITE (RCRA 103) DATE RECEIVED: _____ MONTH DAY YEAR
☒ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION
☒ YES DATE _____ MONTH DAY YEAR
☐ NO
BY (Check all that apply)
☐ A. EPA ☐ B. EPA CONTRACTOR ☐ C. STATE ☐ D. OTHER CONTRACTOR
☐ E. LOCAL HEALTH OFFICIAL ☒ F. OTHER: Broward County Environmental
CONTRACTOR NAME(S): Quality Control Board (BCEQCB)

02 SITE STATUS (Check one)
☐ A. ACTIVE ☒ B. INACTIVE ☐ C. UNKNOWN

03 YEARS OF OPERATION
Pre-1974 1982 UNKNOWN
BEGINNING YEAR ENDING YEAR

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED
Acme Plastics was a manufacturer of plastic letters for the sign industry. Methyl ethyl ketone, paint, styrene and oil were used in the manufacturing process.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

Methyl ethyl ketone (MEK) was used in the plastics manufacturing process. It is not known how much spent MEK was generated or the method of disposal. Rinsewater was discharged and drained into a storm sewer near the building in 1975.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Problems)
☐ A. HIGH (Inspection required promptly)
☐ B. MEDIUM (Inspection required)
☒ C. LOW (Inspection on time available basis)
☐ D. NONE (No further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT Eric Nuzie Costland J. Hill	02 OF (Agency/Organization) FDER	03 TELEPHONE NUMBER 904 1488-0190
04 PERSON RESPONSIBLE FOR ASSESSMENT Willard Murray	05 AGENCY N/A	06 ORGANIZATION E.C. Jordan Co.
	07 TELEPHONE NUMBER 207 775-5401	08 DATE 11 / 7 / 85 MONTH DAY YEAR



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL D9810269

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 10,000+

04 NARRATIVE DESCRIPTION

Rinsing of painted silk screens was done on-site in 1975, the rinsewater mixed with some paint waste and cleaner drained into the back alley to a storm sewer. Contaminants in this rinsewater may have contaminated the groundwater. No groundwater samples have been taken.

01 ☒ B. SURFACE WATER CONTAMINATION

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 10,000+

04 NARRATIVE DESCRIPTION

The site is less than 1 mile south of Cypress Creek Canal. Potential contaminants in the groundwater may have reached nearby surface water. No surface water samples have been taken.

01 ☒ C. CONTAMINATION OF AIR

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 0

04 NARRATIVE DESCRIPTION

No file information is available regarding the present site occupant.

01 ☒ D. FIRE/EXPLOSIVE CONDITIONS

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 0

04 NARRATIVE DESCRIPTION

No file information is available regarding the present site occupant.

01 ☒ E. DIRECT CONTACT

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 0

04 NARRATIVE DESCRIPTION

No file information is available regarding the present site occupant.

01 ☒ F. CONTAMINATION OF SOIL

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 AREA POTENTIALLY AFFECTED: <0.5

04 NARRATIVE DESCRIPTION

Possible spills of materials on-site or discharged rinsewater may have contaminated soil on-site. No soil samples have been taken.

01 ☒ G. DRINKING WATER CONTAMINATION

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 10,000+

04 NARRATIVE DESCRIPTION

Area residents are provided with drinking water from the Fort Lauderdale Executive/Prospect Municipal Wellfield which produces from the shallow and permeable Biscayne aquifer. The site is located 2000 feet east of the nearest wells, and contaminants in the groundwater, may reach the Wellfield.

01 ☐ H. WORKER EXPOSURE/INJURY

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

03 WORKERS POTENTIALLY AFFECTED: 0

04 NARRATIVE DESCRIPTION

Remote potential. The ACME facility is no longer active, thus, causing no potential for worker injury. However, no information is available for the current site occupant.

01 ☒ I. POPULATION EXPOSURE/INJURY

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED


03 POPULATION POTENTIALLY AFFECTED: 10,000+

04 NARRATIVE DESCRIPTION


Area residents may be exposed to hazardous substances via groundwater used for irrigation and other purposes, surface water, drinking water and soils.

ATTACHMENT A
ACME PLASTICS, INC.
FLD981026933
ON-SITE INSPECTIONS

<u>Date</u>	<u>Agency</u>	<u>Samples</u>	<u>Comments</u>
7/30/85	E.C. Jordan Co. for FDER	No	Windshield survey (off-site inspection) found that Acme Plastics was no longer at the site.
7/20/82	FDER	No	No problems noted.
11/10/81	FDER	Yes	Groundwater discharge analysis, no problems noted.
5/19/81	FDER	No	Industrial sludge survey.
9/20/74 to 5/14/80	FDER	No	(15) Inspection Reports.



SCALE 1 : 24000



SITE LOCATION MAP

Acme Plastic, Inc.

750 NW 57 Court

USGS QUAD Ft. Lauderdale North

DATE 1983

ECJORDANCO

REFERENCE LIST

1. Environmental Protection Agency, Federal Register, National Oil and Hazardous Substances Contingency Plan, Part V, July 16, 1982.
2. Farm Chemicals Handbook, Willoughby, OH; Meister Publishing Company, 1982.
3. Florida Department of Environmental Regulation, The Sites List, Summary Status Report, July 1, 1983 - June 30, 1984.
4. Florida Department of Environmental Regulation, 3012 Folder, 2600 Blairstone Road, Tallahassee, Florida. To be used for completion of Preliminary Assessment, Form 2070-12.
5. Florida Department of Natural Resources, Water Resources of Broward County, Report of Investigation No. 65, 1973.
6. Florida Division of Geology, Chemical Quality of Waters of Broward County, Florida, Report of Investigations No. 51, 1968.
7. Florida Geological Survey, Biscayne Aquifer of Dade and Broward Counties, Florida, Report of Investigation No. 17, 1958.
8. Florida Geological Survey, Groundwater Resources of the Oakland Park Area of Eastern Broward County, Florida, Report of Investigation No. 20, 1959.
9. Health and Safety Plan, Florida 3012 Program, E.C. Jordan Co., June 1984.
10. Healy, Henry G., 1977, Public Water Supplies of Selected Municipalities in Florida, 1975: U.S. Geological Survey, Water-Resources Investigations 77-53, p. 309.
11. NUS Project for Performance of Remedial Response Activities at Uncontrolled Hazardous Substance Facilities--Zone 1. NUS Corporation, Superfund Division.
12. NUS Training Manual, Project for Performance of Remedial Response Activities at Uncontrolled Hazardous Substance Facilities--Zone 1, NUS Corporation, Superfund Division.
13. Sax, N. Irving, Dangerous Properties of Industrial Materials, Sixth Edition, Van Nostrand Reinhold Co., 1984.
14. TLVs Threshold Limit Values for Chemical Substances in the Work Environment Adopted by ACGIH for 1983-84, American Conference of Governmental Industrial Hygienists, ISBN: 0-936712-45-7, 1983.
15. U.S. Geological Survey, Topographic Map, 1-24,000 Series.
16. Windholz, M., ed. The Merck Index, an Encyclopedia of Chemicals and Drugs, Rahway, NJ: Merck and Company, Inc., 1976.

7-11-2/30/90

"Rite in the Rain"



ALL-WEATHER

LEVEL

Notebook No. 311

F4-21³⁰ 2³⁰ P.M. 3/30/90

Heme Plastics P.M. 3/30/90
~~Aviation Maintenance, Inc.~~

Fort Lauderdale, Broward County, FLA.

TDD # F4-9002-~~402~~¹⁹ P.M. 3/30/90

Project Manager - ~~Pat Wilson~~ P.M. 3/30/90

Reference 3

"Rite in the Rain" - A unique All-Weather Writing Paper created to shed water and enhance the written image. It is widely used throughout the world for recording critical field data in all kinds of weather.

Available in a variety of standard and custom printed case-bound field books, loose leaf, spiral and stapled notebooks, multi-copy sets and computer papers.

"Rite in the Rain" All-Weather Writing Papers are also available in a wide selection of rolls and sheets for printing and photocopying.

a product of

J. L. DARLING CORPORATION
TACOMA, WA 98421-3696 USA

LOGBOOK REQUIREMENTS
REVISED - NOVEMBER 29, 1988

NOTE: ALL LANGUAGE SHOULD BE FACTUAL AND OBJECTIVE

1. Record on front cover of the Logbook: TDD No., Site Name, Site Location, Project Manager.
2. All entries are made using ink. Draw a single line through errors. Initial and date corrections.
3. Statement of Work Plan, Study Plan, and Safety Plan discussion and distribution to field team with team members' signatures.
4. Record weather conditions and general site information.
5. Sign and date each page. Project Manager is to review and sign off on each logbook daily.
6. Document all calibration and pre-operational checks of equipment. Provide serial numbers of equipment used onsite.
7. Provide reference to Sampling Field Sheets for detailed sampling information.
8. Describe sampling locations in detail and document all changes from project planning documents.
9. Provide a site sketch with sample locations and photo locations.
10. Maintain photo log by completing the stamped information at the end of the logbook.
11. If no site representative is on hand to accept the receipt for samples, an entry to that effect must be placed in the logbook.
12. Record I.D. numbers of COC and receipt for sample forms used. Also record numbers of destroyed documents.
13. Complete SMO information in the space provided.

The undersigned have read and understood
the work plan for this phase of the
site assessment.

Paul Moisan Paul Moisan

Greg Thomas

3/28/90

10:35 - Arrived at site. Weather is partly cloudy and warm. Facility is at the end of N.W. 57th Ct. New company in building - New River Cabinet & Fixture, Inc. appears to be active. Surface water drainage from the facility appears to drain ^{to the} north along R.R. tracks. Property is not fenced and is easily accessible. Land adjacent to property ~~boundaries~~ ⁱⁿ boundaries is industrial with a vacant lot immediately south of site for sale. No stressed vegetation noted. Drums noted in fenced in area at south end of building. Took pictures looking at ⑦ front of building (west side) and ⑧ at south side of building.

P. Moise - 3/28/90

Universal Door
Mfg.

New River Cabinet & Fixture
(750)

loading docks

Parking
(Paved)

Drums
Inc. (800)
Trucks

Vacant lot
for sale

Essex Glass-
Mirror Plastics
Inc.
(700)

~~Drum~~ Drive
Kauf's
(764)

N.W. 57th CT

J. Moore
3-28-90

N
J. Moore
3/28/90

Reference 4

**STATE OF FLORIDA
DEPARTMENT OF NATURAL RESOURCES**

**BUREAU OF GEOLOGY
Robert O. Vernon, Chief**

GEOLOGICAL BULLETIN NO. 51

**THE GEOMORPHOLOGY
OF THE FLORIDA
PENINSULA**

**By
William A. White**

**Published for
BUREAU OF GEOLOGY
DIVISION OF INTERIOR RESOURCES
FLORIDA DEPARTMENT OF NATURAL RESOURCES**

**Tallahassee, Florida
1970**


CONTENTS

Acknowledgement	x
Delineation of Geomorphic features	1
Major Geomorphic Divisions of the Florida Peninsula	2
The Distal or Southern Zone	4
Major peculiarities of the Southern Part of the Florida Peninsula	4
The Florida Keys	15
The High Coral Keys	15
The Low Coral Keys and the Oolite Keys	19
Florida Bay	32
The Islands and Shoals of Florida Bay	24
Drainage of the area adjacent to the north shore of Florida Bay ...	30-31
The Lower west coast of the peninsula	33
The Ten Thousand Islands	43
The Silver Bluff Ridge and Scarp	43
The Miami Ridge	58
Relict Mangrove Islands	59
The Everglades	68
Deposition around the edge of the Everglades	72
Influence of structural lineaments on solution	
in the Distal Zone of the Peninsula	75
Lakes around the edge of the Everglades Trough	78
Reasons for different kinds of Swampy Surface in the Distal Zone ...	82
The Imokalee Rise	84
The Midpeninsular Zone	85
The Atlantic Coastal Lowlands	85
Atlantic Coastal Ridge, Lagoons and Barrier Chain	85
The Eastern Valley	93
The St. Johns River Lake Chain	102
St. Johns River Offset	104
History of the Econlockhatchee River	108
Southern end of the Eastern Valley	109
The Saint Mary's Meander Plain	110
The Central Highlands	110
Origin of Liens of Lakes in ridges of the Central Highlands	114
The Lake Wales Ridge	119
The Intraridge Valley	119
The Higher parts of the Lake Wales Ridge	120
Genetic Relation between Lakes Karst and Relict shoreline	
features in Deland and Crescent City Ridges, Geneva	
Hill, and the Osceola Plain	123
Possibility of a relict cape at Orlando	125
The Marion Upland and the Mount Dora Ridge	128


The Brooksville Ridge	128
The Fairfield and the Ocala Hills	130
The Cotton Plant Ridge	130
The Lake and Sumter Uplands	131
The Polk Upland	132
The Western and Central Valleys	133
The Western Valley	133
The Zephyr Hills, Dunnellon and High Springs Gaps	135
The Lake Harris and Alachua Lake Cross Valleys	135
The Central Valley	136
The Osceola Plain	137
The Caloosahatchee Incline and the DeSoto Plain	139
The Okeechobee Plain	142
The Gulf Coastal Lowlands	142
Terraces of the west side of the peninsula	142
Bell Ridge	148
The Coastal Swamps	148
Aeolean Features of the west side of the Peninsular	149
The Gulf Barrier Chain and Lagoons	153
The Proximal or Northern Zone	155
The Northern Highlands east of the Suwannee River	155
Trail Ridge	158
Florahome Valley	159
Biography	161

Figure

1. Map of Florida physiograph
2. Severed bou Reef Pass on
3. Contours on east of Pinel.
4. Compass dir cypress fore:
5. Rock Reef in photograph
6. Air photos st
7. Canal across of marine de
8. Intricate diss from wave sp
9. Pre-Flandria
10. Long Sound
11. Distal growth
12. Mangrove tre east side of B
13. Air photo sho individual tre of water flow
14. Air photo sho straightness a control, sout
15. Air photo sho southern Dad
16. Foreshortene to offshore pr Florida penin
17. Air photo sho Ten Thousan
18. The Silver Blu it seems to hav during certain
19. West side of B wall of old ex incoherent oo
20. Silver Bluff Sc shore of Biscay
21. Shore of boat
22. Twenty five fo of what is ordi
23. Fossil mangro roots rotted ou



SOIL SURVEY OF
Broward County Area, Florida



**United States Department of Agriculture
Soil Conservation Service**

In cooperation with

**University of Florida
Institute of Food and Agricultural Sciences
Agricultural Experiment Stations
Soil Science Department**

Contents

How this survey was made.....	Page 1
General soil map.....	2
1. Paola-Urban land-St. Lucie association.....	3
2. Immokalee-Urban land-Pompano association.....	3
3. Hallandale-Margate association.....	3
4. Lauderhill-Dania association.....	6
Descriptions of the soils.....	8
Basinger series.....	8
Boca series.....	9
Dania series.....	10
Hallandale series.....	11
Immokalee series.....	12
Lauderhill series.....	13
Margate series.....	14
Paola series.....	15
Plantation series.....	16
Pomello series.....	17
Pompano series.....	18
Sanibel series.....	18
St. Lucie series.....	19
Udorthents.....	19
Urban land.....	20
Use and management of the soils.....	20
Engineering uses of the soils.....	20
Engineering classification systems.....	21
Engineering test data.....	21
Soil properties significant in engineering.....	21
Engineering interpretations.....	23
Use of the soils for farming.....	31
Capability grouping.....	32
Estimated yields.....	33
Use of the soils as wildlife habitat.....	33
Use of the soils for recreational development.....	35
Formation, morphology, and classification of the soils.....	35
Formation of soils.....	35
Parent material.....	35
Climate.....	36
Plants and animals.....	37
Relief.....	37
Time.....	37
Morphology of soils.....	37
Classification of soils.....	37
Laboratory data.....	39
Laboratory methods.....	39
Additional facts about the area.....	42
Climate.....	42
Transportation, markets, and farming.....	43
Water supply and natural resources.....	44
Physiography and drainage.....	44
Literature cited.....	45
Glossary.....	45
Explanation of key phrases.....	47
Guide to mapping units.....	47

Following

Issued July 1976

SOIL SURVEY OF BROWARD COUNTY AREA, FLORIDA

BY ROBERT F. PENDLETON, HERSEL D. DOLLAR, AND LLOYD LAW, JR.,
SOIL CONSERVATION SERVICE

UNITED STATES DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION
SERVICE, IN COOPERATION WITH UNIVERSITY OF FLORIDA, INSTITUTE
OF FOOD AND AGRICULTURAL SCIENCES, AGRICULTURAL EXPERIMENT
STATIONS, SOIL SCIENCE DEPARTMENT

BROWARD COUNTY AREA is in Broward County and the southeastern part of Florida (fig. 1). It




Figure 1.—Location of Broward County Area in Florida.

has a total land area of 189,273 acres or about 296 square miles. Fort Lauderdale is the county seat of Broward County. The survey area is bounded by Dade County on the south, a conservation area on the west, Palm Beach County on the north, and an area defined along Range line 42-43E to Atlantic Boulevard, west on Atlantic Boulevard to Powerline Road, south on Powerline Road to Oakland Park Boulevard, west on Oakland Park Boulevard to Sunshine Parkway, and south on the Sunshine Parkway to the Dade County line.

Most of the survey area is low, nearly level land at an elevation of 2 to 10 feet above sea level. Two sand

ridges are in the area. One is a coastal ridge that extends from Palm Beach County and ends south of Pompano. The other is known as Pine Island and is west of Davie and north of Cooper City. This ridge consists of only about 400 acres but is at the highest elevation, 29 feet, in the Area. The average temperature is 75.4° F. Rainfall is abundant, but is unevenly distributed.

The county had a population of 620,000 people in 1970.¹ Almost all of the people live east of the conservation area.

Generally, farm activity has diminished, but some citrus crops, winter truck crops, and cattle are produced.

The Area is very popular with tourists and retired persons because of the warm climate in winter and the various available recreational facilities.

How This Survey Was Made

Soil scientists made this survey to learn what kinds of soil are in the Broward County Area, where they are located, and how they can be used. The soil scientists went into the county knowing they likely would find many soils they had already seen and perhaps some they had not. They observed the steepness, length, and shape of slopes, the size and speed of streams, the kinds of native plants or crops, the kinds of rock, and many facts about the soils. They dug many holes to expose soil profiles. A profile is the sequence of natural layers, or horizons, in a soil; it extends from the surface down into the parent material that has not been changed much by leaching or by the action of plant roots.

The soil scientists made comparisons among the profiles they studied, and they compared these profiles with those in counties nearby and in places more distant. They classified and named the soils according to nationwide, uniform procedures. The *soil series* and the *soil phase* are the categories of soil classification most used in a local survey.

Soils that have profiles almost alike make up a soil series. Except for different textures in the surface

¹ This figure is taken from statistical data of the U.S. Department of Commerce, Bureau of the Census.

cation exchange capacity and then multiplying by 100.

Organic matter was determined by a modification of the Walkley-Black wet-combustion method as outlined in procedure 6A1a. Total nitrogen was obtained by the semi-micro Kjeldahl method as shown in procedure 6B2a. Resistivity (ohm/em) or an "R" value was obtained using a Model 100 Corrosion Tester. The corrosion potential or a "C" value that was obtained from the manufacturer's tables is directly related to the "R" value. The smaller the "C" value, the less the corrosion and the greater the expectancy of pipe life. Generally, C values range from 1 to 10, and pipe life ranges accordingly from 20 to 2 years.

Bulk density, hydraulic conductivity (saturated), and water retention at 0.10 and 0.33 bar were measured on 3 by 5.4 centimeter cylindrical (undisturbed) soil cores. Water retention at 15-bar suction was determined on disturbed or loose soil samples by procedure 4B2.

Water retention difference was calculated using the formula

$$\text{WRD (in/in)} = \frac{\frac{1}{3} - (\text{or } \frac{1}{10}) \text{ bar } \% - 15 - \text{bar } \%}{100}$$

x bulk density, moist. $\frac{1}{10}$ bar was used for sandy soils and $\frac{1}{3}$ bar for organic soils. Water retention difference is considered by many to closely approximate available water capacity.

Additional Facts About the Area

Soil is intimately associated with its environment. The interaction of all factors determines the overall behavior of a soil for a given use. This section discusses briefly the major factors of the environment other than those that affect the use and management of soils. The factors discussed are climate; transportation, markets, and farming; water supply and natural resources; and physiography and drainage.

Climate¹⁰

The climate of Broward County is characterized by long, warm, humid summers and mild winters. The moderating influence of the waters of the Atlantic on maximum temperatures in summer and minimum temperatures in winter is quite strong along the immediate coast but diminishes noticeably a few miles inland. The moderation of the coastal winter temperatures gives this section of the survey area a tropical climate (temperatures of coldest month higher than 64.4° F), while the rest is designated as humid subtropical.

Rainfall also has a much greater variation in an east-west direction than it has in a north-south direction. Precipitation occurs during all seasons but on the basis of mean monthly totals of precipitation, a rainy season of 5 months from June through October brings

nearly 65 percent of the annual rainfall and a relatively dry season of 5 months from November through March produces only about 20 percent of the annual total. Average annual rainfall totals range from 60 inches along the coastal sections to nearly 64 inches a few miles inland, and then diminish to 50 inches along the western border of Broward County.

Most summer rainfall comes from showers and thunderstorms of short duration. They are sometimes heavy, with 2 or 3 inches of rain falling within a period of 1 to 2 hours. Day-long rains in summer are rare. When they occur, they are almost always associated with tropical storms. Winter and spring rains are not generally so intense as summer thundershowers. A 24-hour rainfall of almost 9 inches may be expected to occur sometime during the year in about 1 year in 10 on the average.

Hail falls occasionally in thunderstorms but the hailstones are generally small and seldom cause much damage. Fourteen tornadoes were reported in Broward County during the 12-year period 1959-71.

Temperature and precipitation data for the period 1962-71 are shown in table 17. The data recorded at the Fort Lauderdale Experiment Station are representative of weather conditions in the eastern section of Broward County, but away from the immediate influences of the Atlantic. Table 18 gives a comparison with other weather stations within Broward County. The Experiment Station is located 5 miles southwest of the Fort Lauderdale Post Office, while the Dixie Water Plant is within the city limits, 2 miles southwest of the Post Office. The Bahia Mar observations are taken at the Yacht Club on the ocean, 3 miles east of the Post Office. North New River Canal No. 2 is a weather station that collects rainfall data only. It is located on the northern border of the county, centered midway between its eastern and western boundaries.

Summer temperatures have few day-to-day variations, and temperatures as high as 98° F. are rare. In 45 years of record at the Dixie Water Plant, only one reading of 100° has been recorded. Twenty years of observation show a record high of 98° at the Experiment Station and 96° at Bahia Mar.

Winter minimum temperatures have considerable day-to-day variations due largely to periodic invasions of cold, dry air that has moved southward from Canada. At the Experiment Station, temperatures of 32° or below have been observed on only 11 days during the past 10 years. In 3 of the 10 years, no freezing temperatures have been observed. Data from stations run by the Federal-State Frost Warning Service show that in the 30-year period 1937-67, there were 25 nights on which the temperatures reached 32° or below the coast, and 75 nights inland along the western edge of Broward County. Calculations show that in the same period there were 100 hours with temperatures of 32° or below along the coast, increasing to 300 hours inland. The lowest temperature reported in the Fort Lauderdale area during the last 45 years was 28°. Table 19 gives the record of low temperatures at Davie, a Frost Warning Station located in the interior southeastern section of Broward County. This temperature record can be considered representative of the climate for truck farming in the eastern sections of the survey area.

¹⁰ By JAMES T. BRADLEY, climatologist for Florida, National Weather Service, U.S. Department of Commerce. For convenience in presentation this section includes climate data for all of Broward County.

TABLE 19.—Record of low temperatures

[Period of

Temperature °F	Percent of seasons at or below various temperatures before—						
	November 20	December 10	December 30	January 19	February 18	March 10	March 30
36	0	23	57	87	100	100	100
32	0	13	33	57	77	83	83
28	0	0	7	17	33	33	33
26	0	0	7	7	17	17	17
24	0	0	0	0	3	3	3

Four airports are available for use—Fort Lauderdale-Hollywood International Airport, Fort Lauderdale Executive Airport, Pompano Beach Airport, and North Perry Airport. Only Fort Lauderdale International Airport has scheduled commercial airline flights. The other airports are mostly for private planes.

The largest state owned fresh-vegetable market in Florida is the Pompano State Farmers' Market. This market handles vegetables from the survey area and from the southern part of Palm Beach County. Most of the citrus is processed in other counties. More grapefruit is consumed than is produced in the county.

Not much farming was practiced in the Broward County Area before 1910. Drainage was established with the formation of the Napoleon B. Broward Drainage District. After drainage was established, citrus groves were planted between the New River and South New River Canals. Most of the winter vegetable crops were grown in the same area, but planting soon spread primarily to the north as the area was developed (9). According to the 1950 Census of Agriculture, approximately 700 farms and 45 dairies were in Broward County in 1950. By 1969, the number had decreased to 291 farms and 8 dairies. Farming in the Area generally is still on the decrease.

This is one of the few places in the United States that has either a tropical or humid subtropical climate. A large percentage of the soils are nearly level, poorly drained, and infertile. Another fairly large group of soils are organic and nearly level, very poorly drained, and relatively fertile. With drainage and proper fertilization, all of these soils produce excellent winter truck crops.

The coastal areas have excellent facilities for fishing and boating.

Water Supply and Natural Resources

The water supply for the cities in the Broward County Area comes primarily from municipal wells. Many private wells are used mostly for watering lawns. Because porous limestone is below most of the soils, water can move laterally for long distances. The water in the canals can be regulated to help recharge the ground water during dry periods.

Although most of the Area receives about 60 inches of rainfall annually, this amount may not be sufficient

to provide water needs in the future. The main alternate source could be Lake Okeechobee to the north of the survey area.

Climate is considered one of the most important natural resources of the Area.

Physiography and Drainage

The Broward County Area can be divided into three general parts based on differences in physiography and soils.

The western part is a nearly level, generally treeless sawgrass plain that appears to be flat. The soils are organic and overlies limestone. In many places the soils are shallow. Under natural conditions, water stood on these soils for months and only during extremely dry seasons was the surface exposed. Today, these soils have been drained, and water stands on the surface for only short periods. With drainage, the organic soils are subject to oxidation and subsidence. When exposed to air, organic matter is oxidized or slowly burned up, and this gradual loss of organic matter results in subsidence or a lowering of surface elevation. Also, during dry seasons, wildfires have burned some of the organic surface soil, and decreased the thickness of the organic material.

Very little of the organic soils are presently farmed. A few acres are in improved pasture. In recent years, after some drainage, several types of trees have become established. These trees are melaleuca, Australian pine, and waxmyrtle. One method used for developing the organic soils for urban use removes the organic material and adds fill consisting of rock or sand.

The central part consists of nearly level, grassy areas interspersed with small ponds. The soils here are wet and sandy and are underlain by limestone. Before drainage, water stood on these soils for several months each year. The original vegetation was water-tolerant grasses and a few cypress stands. In the higher areas, pine and palmetto were common. These areas are now farmed, and with drainage produce excellent pasture and truck crops.

This is also an area of rapid urban development. The underlying limestone is mostly porous, and water moves through it laterally for long distances. Water-control ditches can be further apart in these soils than in soils underlain by sand or loamy material. For urban

at Davie in Broward County

record 1937-67]

Percent of seasons at or below various temperatures after—						
November 20	December 10	December 30	January 19	February 18	March 10	March 30
100	100	100	83	50	13	0
83	80	73	50	17	3	0
37	37	30	20	3	0	0
17	17	10	17	0	0	0
3	3	3	3	0	0	0

development, fill is commonly added to raise the elevation to such a level that water does not cover the soil surface.

The eastern part is made up of low, sandy ridges, a part of which is commonly referred to as flatwoods. The vegetation is mostly pine, palmetto, and native grasses. The flatwoods part is made up of deep, poorly drained, nearly level, sandy soils. These soils have been used mostly for truck crops and pasture, but are rapidly being developed for urban uses. They require drainage, and fill is added to low areas so that the entire acreage can be developed. The other part is made up of deep, excessively drained or well-drained, sandy soils, many of which, are developed for urban uses.

The major drainage systems in the Area flow from west to east and drain into the Atlantic Ocean. These systems are the Hillsboro Canal at the Palm Beach-Broward County line, the Pompano Canal at Margate, the Midriver Canal at Lauderhill, the North New River Canal at Davie, and C-9 at the Dade County line. These canals are under the control of the Central and Southern Florida Flood Central District.

of some Florida soils ii. exchangeable and titratable acidity. Soil and Crop Science Society of Florida Proceedings 31: 149-154.

Glossary

Association, soil. A group of soils geographically associated in a characteristic repeating pattern.

Available water capacity (also termed available moisture capacity). The capacity of soils to hold water available for use by most plants. It is commonly defined as the difference between the amount of soil water at field capacity and the amount at wilting point. It is commonly expressed as inches of water per inch of soil.

Base saturation. The degree to which material that has base-exchange properties is saturated with exchangeable cations other than hydrogen, expressed as a percentage of the cation-exchange capacity.

Clay. As a soil separate, the mineral soil particles less than 0.002 millimeter in diameter. As a soil textural class, soil material that is 40 percent or more clay, less than 45 percent sand, and less than 40 percent silt.

Complex, soil. A mapping unit consisting of different kinds of soils that occur in such small individual areas or in such an intricate pattern that they cannot be shown separately on a publishable soil map.

Consistence, soil. The feel of the soil and the ease with which a lump can be crushed by the fingers. Terms commonly used to describe consistence are—

Loose.—Noncoherent when dry or moist; does not hold together in a mass.

Friable.—When moist, crushes easily under gentle pressure between thumb and forefinger and can be pressed together into a lump.

Firm.—When moist, crushes under moderate pressure between thumb and forefinger, but resistance is distinctly noticeable.

Plastic.—When wet, readily deformed by moderate pressure but can be pressed into a lump; will form a "wire" when rolled between thumb and forefinger.

Sticky.—When wet, adheres to other material, and tends to stretch somewhat and pull apart, rather than to pull free from other material.

Hard.—When dry, moderately resistant to pressure; can be broken with difficulty between thumb and forefinger.

Soft.—When dry, breaks into powder or individual grains under very slight pressure.

Cemented.—Hard and brittle; little affected by moistening.

Drainage class (natural). Refers to the conditions of frequency and duration of periods of saturation or partial saturation that existed during the development of the soil, as opposed to altered drainage, which is commonly the result of artificial drainage or irrigation but may be caused by the sudden deepening of channels or the blocking of drainage outlets. Seven different classes of natural soil drainage are recognized.

Literature Cited

- (1) American Association of State Highway Officials. 1961. Standard specifications for highway materials and methods of sampling and testing. Ed. 8, 2 v., illus.
- (2) Bouyoucos, G. J. 1962. Hydrometer method improved for making particle size analyses of soils. Agron. Jour. 54: 464-465.
- (3) Cooke, C., Wythe. 1945. Geology of Florida. Fla. State Dept. of Conserv. and Fla. Geol. Survey, Geol. Bul. 29, 339 pp., illus.
- (4) Simonson, Roy W. 1962. Soil classification in the United States. Sci. 137, 1027-1034, illus.
- (5) United States Department of Agriculture. 1951. Soil survey manual. U.S. Dept. Agr. Handb. No. 18, 503 pp., illus.
- (6) ———. 1960. Soil classification, a comprehensive system, 7th approximation. 265 pp., illus. [Supplements issued in March 1967 and in September 1968]
- (7) ———. 1972. Soil survey laboratory methods and procedures for collecting soil samples. Soil Survey Investigations Report No. 1 (Revised Edition).
- (8) United States Department of Defense. 1968. Unified soil classification system for roads, airfields, embankments, and foundations. MIL-STD-619B, 30 pp., illus.
- (9) Weidling, Philip and Burghard, August. 1966. Checkered sunshine; the story of Fort Lauderdale, 1793-1955. Gainesville, University of Florida Press, 296 pp., illus.
- (10) Zelazny, L. W. and Fiskell, J. G. A. 1972. Acidic properites

Water Resources of Southeastern Florida

By GARALD G. PARKER, G. E. FERGUSON, S. K. LOVE, and others

WITH SPECIAL REFERENCE TO THE GEOLOGY AND GROUND
WATER OF THE MIAMI AREA

GEOLOGICAL SURVEY WATER-SUPPLY PAPER 1255

*Prepared in cooperation with the Florida
Geological Survey, Dade County, cities
of Miami and Miami Beach, and other
agencies*






Figure 25. --Close-up view of one of the larger solution holes in Dade County.

and downward movement of corrosive waters. (See figs. 15, 25 and 26.)

Apparently, no original cavity is needed to start a solution hole, though the existence of a ready-made hole hastens the process. It has been suggested that many vertical solution holes begin to be dissolved along taproots of trees, and possibly some holes do originate in this fashion, but it is not the most common way. On the surface of hard limestone or soft calcareous clayey marl the first effects of solution appear as small surficial pits resembling raindrop marks in mud. These pits gradually deepen, many retaining their rounded outlines. Without visible outlet along the sides or bottom, they later become tubes which enlarge into holes of various shapes and sizes, but generally they develop vertically.

The work of solution is evident wherever outcrops of rock occur, as on the bare limestone surface south of Miami or in the Big Cypress Swamp, in canals and street cuts, in borrow ditches and rock quarries, or in river and creek banks. In large areas of southern Florida it is evident that at least one-fourth of the total volume of limestone, once more or less solid rock, is now occupied by solution holes, generally filled with sand. (See fig. 26.) Trees blown over by hurricanes rip up rock with their roots, thus leaving a new and localized depression for concentration of rain water and the start of active solution holes. Adjacent holes enlarge, coalesce, and become increasingly effective in draining surface water underground. Many solution depressions of this kind,

Reference 7



NCE . Environmental Science Services Administration . Environmental Data Service




U.S. DEPARTMENT OF COMMERCE
C. R. Smith, Secretary

ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION
Robert M. White, Administrator


ENVIRONMENTAL DATA SERVICE
Woodrow C. Jacobs, Director

JUNE 1968

REPRINTED BY THE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
1983



LAKE EVAPORATION



TECHNICAL PAPER NO. 40

RAINFALL FREQUENCY ATLAS OF THE UNITED STATES
for Durations from 30 Minutes to 24 Hours and
Return Periods from 1 to 100 Years

Prepared by

DAVID M. HENSHFIELD

Cooperative Studies Section, Hydrologic Services Division

for

Engineering Division, Soil Conservation Service

U. S. Department of Agriculture

Reference 8



PROPERTY
111

Reference 9

GEOLOGY OF THE SURFICIAL AQUIFER SYSTEM


BROWARD COUNTY, FLORIDA

LITHOLOGIC LOGS

By Carmen R. Causarás

U.S. GEOLOGICAL SURVEY

WATER-RESOURCES INVESTIGATIONS REPORT 84-4068



6-2327
SECTION
D-D

HOLLYWOOD BLVD

SOUTH NEW RIVER
CANAL

NORTH NEW RIVER
CANAL

6-2345
SECTION
C-C

FLORIDA'S
TURNPIKE

SECTION
B-B
6-2342
US-441

SECTION
A-A'
6-2323

HILLSBORO CANAL

EXPLANATION

	Fill
	Peat or muck
	Sand
	Sandstone
	Detrital carbonate sand
	Concretions
	Shell
	Silt
	Clay
	Claystone or siltstone
	Micrite (Limemud)
	Limestone
	Oolitic limestone
	Coralline limestone or Biolithite

GEOLOGIC FORMATIONS

Qp	Pamlico Formation
Qm	Miami Oolite
Qa	Anastasia Formation
Qk	Key Largo Limestone
Qf	Fort Thompson Formation
Tt	Tamiami Formation
Th	Hawthorn Formation
Tth	Tamiami Formation undifferentiated
—	Formation boundary

G-2314

Test well and number

NGVD National Geodetic Vertical Datum of 1929 (formerly called mean sea level)

0 10 20 30 Miles


0 10 20 30 40 Kilometers

Vertical Scale Greatly Exaggerated

BISCAYNE AQUIFER, SOUTHEAST FLORIDA

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations 78-107



Prepared in cooperation with
U.S. ENVIRONMENTAL PROTECTION AGENCY



BIBLIOGRAPHIC DATA SHEET	1. Report No.	2.	3. Recipient's Accession No.
4. Title and Subtitle BISCAYNE AQUIFER, SOUTHEAST FLORIDA		5. Report Date September 1975	
7. Author(s) H. Klein, J. E. Hull		8. Performing Organization Rep. No. USGS/WRI 75-107	
9. Performing Organization Name and Address U.S. Geological Survey 7815 Coral Way, Suite 110 Miami, Florida 33155		10. Project/Task/Work Unit No.	
		11. Contract/Grant No.	
12. Sponsoring Organization Name and Address U.S. Geological Survey, Water Resources Division 325 John Knox Road, Suite F-240 Tallahassee, Florida 32303		13. Type of Report & Period Covered	
		14.	
15. Supplementary Notes Prepared in cooperation with the U.S. Environmental Protection Agency			
16. Abstracts Peak daily pumpage from the highly permeable, unconfined Biscayne aquifer for public water-supply systems in southeast Florida in 1975 was about 500 million gallons. Another 165 million gallons was withdrawn daily for irrigation. Recharge to the aquifer is primarily by local rainfall. Discharge is by evapotranspiration, canal drainage, coastal seepage, and pumping. Pollutants can enter the aquifer by direct infiltration from land surface or controlled canals, septic-tank and other drainfields, drainage wells, and solid-waste dumps. Most of the pollutants are concentrated in the upper 20 to 30 feet of the aquifer; public supply wells generally range in depth from about 75 to 150 feet. Dilution, dispersion, and adsorption tend to reduce the concentrations. Seasonal heavy rainfall and canal discharge accelerate ground-water circulation, thereby tending to dilute and flush upper zones of the aquifer. The ultimate fate of pollutants in the aquifer is the ocean, although some may be adsorbed by the aquifer materials en route to the ocean, and some are diverted to pumping wells.			
17. Key Words and Document Analysis. 17a. Descriptors Southeast Florida, Aquifer characteristics, *Ground-water quality, *Municipal water systems, *Water pollution, Urban runoff, Septic-tank effluent, Leachate, *Ground-water flow, Dilution, Unconfined ground water			
17b. Identifiers/Open-Ended Terms Dade County, Broward County, *Biscayne aquifer, Sole-source aquifer, Safe Drinking Water Act			
17c. CORATI Field/Group			
18. Availability Statement		19. Security Class (This Report) Unclassified	20. No. of Pages 32
		21. Security Class (This Page) Unclassified	22. Price

UNITED STATES DEPARTMENT OF THE INTERIOR

CECIL D. ANDRUS, Secretary

GEOLOGICAL SURVEY

H. William Menard, Director

For additional information write to:

**U.S. Geological Survey
325 John Knox Road
Suite F-240
Tallahassee, Florida 32303**

BISCAYNE AQUIFER

Description

The Biscayne aquifer supplies all municipal water supply systems from south Palm Beach County southward (fig. 1), including the system for the Florida Keys which is supplied chiefly by pipeline from the mainland. It is a highly permeable wedge-shaped unconfined aquifer that is more than 200 ft (feet) thick in coastal Broward County and thins to an edge 35 to 40 mi (miles) inland in the Everglades (fig. 2). The aquifer forms an important unit of the hydrologic system of southeast Florida (fig. 3), which is managed by the South Florida Water Management District (SFWMD).

The Biscayne aquifer is composed of limestone, sandstone, and sand. In south and west Dade County the aquifer is primarily limestone and sandstone, but in north Dade County, Broward County and south Palm Beach County the aquifer is primarily sand. Generally, the sand content increases to the north and east.

In Dade County (fig. 4) oolitic limestone and quartz sand form the upper part of the aquifer (Parker and others, 1955, Plate 4). The limestone is thickest along the coast, possibly as much as 40 ft., but the base is usually less than 20 ft below sea level. Inland, the oolitic limestone thins and then disappears beneath the peat soil of the Everglades. Oolitic limestone is usually cross-bedded.

Fine to medium grained sand fills solution cavities in the oolitic limestone. Parker and others (1955, p. 102) indicated that the solution cavities occupy a significant volume of the limestone, causing it to have high horizontal and vertical permeabilities. It is the high vertical permeability that permits rapid infiltration of rainfall to the water table. Where the limestone does not crop out, it is covered by quartz sand (fig. 4) which also permits rapid infiltration of rainfall.

In the east part of Dade County, extending north as far as Fort Lauderdale, the lower part of the oolitic limestone contains bryozoans (Hoffmeister, 1974, p. 39). The bryozoan section slopes upward to the west to emerge at the surface in the Everglades. Near the coast the bryozoan section is as much as 10 ft thick (Hoffmeister, 1974, p. 39); it thins to the west beyond the east boundary of Collier County. The bryozoan limestone is also riddled with cavities which contribute to its high horizontal and vertical permeability.

Below the bryozoan layer, the Biscayne aquifer is composed of hard limestone containing numerous cavities, often cavernous. Because of the extremely high permeability of this limestone, all large-capacity wells are completed in this part of the aquifer, generally 40 to 100 ft below the land surface. The cavernous section generally does not contain loose sand. The aquifer does, however, contain thin interbedded layers

of hard, dense limestone in south Dade County, interior parts of Dade County and southwest Broward County. The dense layers probably are discontinuous and may locally retard, but do not prevent the vertical circulation of ground water. Beneath the coastal areas unconsolidated quartz sand separates the bryozoan limestone from the deeper hard limestone. The sand content increases northward which results in a corresponding decrease in overall transmissivity of the aquifer.

Parker and others (1955, p. 160) stated that the Biscayne aquifer "is the most productive of the shallow nonartesian aquifers in the area and is one of the most permeable in the world". He suggested that in east Dade County the transmissivity (hydraulic conductivity x saturated thickness = transmissivity) of the aquifer ranges from 4 to 15 million gallons per day per foot (Mgal/d/ft) (5×10^5 to 2.0×10^6 ft²/d). He applied a median value of 5 (Mgal/d/ft) (6.7×10^5 ft²/d) (Parker and others, 1955, p. 270). These values were obtained from aquifer tests using high-capacity wells, and by analyzing water-table contours adjacent to canals and in well-field areas. Storage coefficients from aquifer tests ranged from 0.047 to 0.247 (Parker and others, 1955, table 16).

The approximate areal distribution of transmissivity of the aquifer is shown in figure 5. Along the coast and in the northern part of southeast Florida the aquifer is thickest, but because it is composed mainly of sandy material, the transmissivity is lower. In central and south Dade County the aquifer is thinner, but the hydraulic conductivity is high because of the cavernous limestone; the transmissivity is, therefore, high. The decrease in transmissivity to the west is due to the thinning of the aquifer.

The transmissivity ranges from about 3 Mgal/d per foot (4.0×10^5 ft²/d) in southeast Broward County to 0.4 Mgal/d per foot (5.4×10^4 ft²/d) in the northeast coastal Broward County (Sherwood and others, 1973, p. 66-67) and in the vicinity of Boca Raton (McCoy and Hardee, 1970, p. 25). Values increase to about 4 Mgal/d per foot (5.4×10^5 ft²/d) (Sherwood and others, 1973, p. 66) in interior parts of southern Broward County. In Boca Raton, fine and medium sand extends to at least 60 ft below the surface. Permeable limestone at greater depth is discontinuous and becomes increasingly sandy north of Boca Raton (McCoy and Hardee, 1970, p. 7-11). Storage coefficients in Broward County are as high as 0.34 (Sherwood and others, 1973, p. 67).

Soil Cover

The soil that covers southeast Florida is of hydrologic importance because it controls the infiltration of rainfall, the operation of septic tanks, and indirectly relates to the quality of the ground water. The infiltration of rainfall is rapid in areas covered by sand or where soil is absent; infiltration is retarded in areas covered by marl or clayey soil.

In the agricultural areas of south and interior Dade County, irrigation wells are usually rotary drilled to depths of 25 to 35 ft. Casing is not required because the aquifer is solely limestone. Hundreds of these wells are drilled at spacings as small as 300 ft. A large capacity irrigation pump mounted on a truck is moved from well to well and each is pumped for short intervals at rates of 500 to 1,000 gpm.

Thousands of small diameter (2-inch) wells are used throughout the year for irrigation of residential lawns and shrubs. These wells, about 20 to 50 ft deep, are normally pumped at rates of 25 to 40 gpm. In areas near the coast or adjacent to tidal canals no fresh ground water is available so residences use municipal water for lawn irrigation. Shallow wells of small diameter are also used for domestic supplies in areas not serviced by municipal systems.

Recharge and Discharge

The Biscayne aquifer is recharged principally by rainfall. The average annual rainfall in the lower east coast area varies areally from 58 to 64 in; the annual extremes experienced are 29 in and 106 in (Leach and others, 1972, p. 9-10). The rainy season, June - October, contributes about 70 percent of the total. During this period heavy rains are associated with tropical disturbances and frequent short, local downpours. Light to moderate rainfall during the dry season is associated with cold fronts moving southward through Florida.

The oolitic limestone and sand that form the upper surface of the aquifer readily absorb rainfall and move it rapidly to the water table. The rapid response of the water table to rainfall in the Miami area is indicated in figure 9. Infiltration of rainfall is retarded but not prevented in interior parts of Dade and Broward Counties where thin marl deposits cover the surface, and along the shallow elongate depressions that dissect the urban area. Other sources of recharge to the aquifer are: (1) Connate ground water of inferior quality (Parker and others, 1955, fig. 221) along the upper reaches of the Miami, the North New River, and the Hillsboro Canals in Broward and Palm Beach Counties (northwest of the limits of the Biscayne aquifer) that is transferred eastward during dry seasons; (2) Water from Lake Okeechobee released by the SFWMD into the Miami Canal during the later weeks of the dry seasons to replenish the Miami area; and (3) Effluent from septic tanks, certain sewage treatment plant and disposal ponds scattered throughout the urban area.

Parker and others (1955) and Mayer (1971) estimated that 20 in of the approximately 60 in of annual rainfall in Dade County is lost directly by evaporation, about 20 in is lost by evapotranspiration after infiltration, 16 to 18 in is discharged by canals and by coastal seepage, and the remainder is utilized by man. Sherwood and others (1973, p. 49) indicated comparable values for Broward County. Thus, nearly 50 percent of the rainfall that infiltrates the Biscayne aquifer is discharged to the ocean, a reflection of the high degree of connection between the aquifer and the canal system.

Reference 11

STATE BOARD OF

FLORIDA GEOLOGICAL SURVEY

REPORT OF INVESTIGATIONS NO. 17

RESCUE ATTEMPT IN
MINE AND HUNTER, FLORIDA

JOSEPH C. SCHMIDT, ROBERT L. HAYES, and NEVIN D. HOY

U. S. GEOLOGICAL SURVEY

REF.

TABLE OF CONTENTS

	Page	Figure
Abstract	1	1 Map of County aquifer
Introduction	1	
Location and geography of area	1	2 Structural showing
Purpose and scope of investigation	3	3 Geologic
Previous investigations	3	4 West-east
Personnel and acknowledgments	4	5 West-east
Biscayne aquifer	4	6 North-south
Definition	4	7 Map of geologic
Areal extent and thickness	5	8 West-east Tamiami
Geologic formations composing the Biscayne aquifer	7	9 North-south
General features	7	10 Map of eastern
Miocene series	10	11 Graphs rainfall
Tamiami formation	10	Station
Pliocene series	11	12 Chart of selected
Caloosahatchee marl	11	13 Map showing location
Pleistocene series	11	14 Low-station County
Fort Thompson formation	11	15 Low-station April
Key Largo limestone	20	16 High-station 11-12
Anastasia formation	21	17 Map showing Miami
Miami oolite	23	18 Map showing through
Pamlico sand	24	19 Profile of in 194
Ground-water occurrence	24	20 Profile of Canal
General features	24	21 Profile of in 19
Shape and slope of the water table	25	22 Profile of in 19
Fluctuation of the water table	26	23 Profile of the T
Recharge and discharge	36	24 Profile of Canal
Hydrologic characteristics of the Biscayne aquifer	37	
Quality of the water	41	
Salt-water contamination	42	
Adequacy of supply	45	
Selected references	55	




Figure 12. Chart of comparative average monthly water levels in selected wells.





Figure 1



ected wells.




Figure 13. Map showing location of certain observation wells and locations of large municipal well fields.

p. 519-524) and as reported by Parker (Parker, Ferguson, Love, and others, 1955, p. 239-274) are summarized in the following table (see fig. 14 for location of test sites).

Test site	Range in computed coefficient of transmissibility (gpd/ft)	
	Lowest	Highest
S 1	3,250,000	4,300,000
G 551	9,000,000	14,000,000
G 552	2,800,000	5,700,000
G 553	2,500,000	3,900,000
G 218	3,900,000	4,400,000

At all the test sites the Miami oolite forms the upper part of the Biscayne aquifer, and at most of them it is underlain by a bed of sand. The permeability of the oolite and sand is lower than that of the underlying cavernous limestone of the Fort Thompson formation and thus acts as a leaky roof during the pumping of a well, and the formation initially acts as an artesian aquifer. The Bessel function then can be used in the computations using formulas developed by Jacob (1945, p. 198-208). John G. Ferris (1950, personal communication) determined the following values from the test data:

Well No.	Coefficient of transmissibility (gpd/ft)
S 1	3,200,000
G 551	9,700,000
G 552	3,200,000
G 553	3,200,000

The T value of the test for well G 551 by both calculations is inconsistent with the values for the other tests. The results of the other three tests using the Bessel function are extraordinarily consistent considering the character of the aquifer. The permeability of the Biscayne aquifer probably averages between 50,000 and 70,000 gallons per day per square foot, according to Parker (1951). No satisfactory computation of the storage coefficient has yet been obtained.

Several assumptions concerning the aquifer must be applied in using formulas to determine these coefficients: (1) the aquifer is homogeneous and isotropic and transmits water with equal readiness in all directions; (2) the discharging well penetrates the entire thickness of the aquifer; (3) there is no turbulent flow within the aquifer, and during the pumping there is no vertical convergence of flow lines toward the pumped well; and (4) water is discharged from storage instantaneously with reduction in head.

Reference 12

R. Allan Freeze

Department of Geological Sciences
University of British Columbia
Vancouver, British Columbia

John A. Cherry

Department of Earth Sciences
University of Waterloo
Waterloo, Ontario

GROUNDWATER

Prentice-Hall, Inc.
Englewood Cliffs, New Jersey 07632

ee conductance
l. so petroleum
3) is substituted

(2.29)

at will lead to
er a hydraulic
rcy is approxi-

d for hydraulic
in terms of Eq.

in regard to this
cient. However,
led this formal
ure of measure-
it can influence
3). The effect is
ll makes good
e been carried
ement are very
pendent on the
ther than con-

ity and perme-
gical materials.
9) review. The
lic conductivity
ers that take on
ty implies that
be very useful.
e probably has

common units
be converted to
ion from ft² to

Table 2.2 Range of Values of Hydraulic Conductivity and Permeability

	Rocks	Unconsolidated deposits	k (darcy)	k (cm ²)	K (cm/s)	K (m/s)	K (gal/day/ft ²)
			10^5	10^{-3}	10^2	1	
			10^{-3}	10^{-4}	1	10^{-1}	10^5
			10^3	10^{-5}	1	10^{-2}	10^3
			10^2	10^{-6}	10^{-1}	10^{-3}	10^4
			10	10^{-7}	10^{-2}	10^{-4}	10^3
			1	10^{-8}	10^{-3}	10^{-5}	10^2
			10^{-1}	10^{-9}	10^{-4}	10^{-6}	10
			10^{-2}	10^{-10}	10^{-5}	10^{-7}	1
			10^{-3}	10^{-11}	10^{-6}	10^{-8}	10^{-1}
			10^{-4}	10^{-12}	10^{-7}	10^{-9}	10^{-2}
			10^{-5}	10^{-13}	10^{-8}	10^{-10}	10^{-3}
			10^{-6}	10^{-14}	10^{-9}	10^{-11}	10^{-4}
			10^{-7}	10^{-15}	10^{-10}	10^{-12}	10^{-5}
			10^{-8}	10^{-16}	10^{-11}	10^{-13}	10^{-6}
							10^{-7}

Table 2.3 Conversion Factors for Permeability and Hydraulic Conductivity Units

	Permeability, k^a			Hydraulic conductivity, K		
	cm ²	ft ²	darcy	m/s	ft/s	U.S. gal/day/ft ²
cm ²	1	1.08×10^{-3}	1.01×10^8	9.80×10^2	3.22×10^3	1.85×10^9
ft ²	9.29×10^2	1	9.42×10^{10}	9.11×10^3	2.99×10^6	1.71×10^{12}
darcy	9.87×10^{-9}	1.06×10^{-11}	1	9.66×10^{-6}	3.17×10^{-5}	1.82×10^1
m/s	1.02×10^{-3}	1.10×10^{-6}	1.04×10^3	1	3.28	2.12×10^6
ft/s	3.11×10^{-4}	3.35×10^{-7}	3.15×10^6	3.05×10^{-1}	1	6.46×10^3
U.S. gal/day/ft ²	5.42×10^{-10}	5.83×10^{-13}	5.49×10^{-2}	4.72×10^{-7}	1.55×10^{-6}	1

^aTo obtain k in ft², multiply k in cm² by 1.08×10^{-3} .

Freeze, R.A., and J.A. Cherry, "Groundwater,"
Prentice-Hall, Inc., Englewood Cliffs, N.J., 1979.

Reference 13

STATE OF FLORIDA
DEPARTMENT OF NATURAL RESOURCES
Harmon Shields, Executive Director

DIVISION OF INTERIOR RESOURCES
Charles M. Sanders, Director

BUREAU OF GEOLOGY
Charles W. Hendry, Jr., Chief

Report of Investigations No. 75

**EVALUATION OF HYDRAULIC
CHARACTERISTICS OF A DEEP ARTESIAN AQUIFER FROM
NATURAL WATER - LEVEL FLUCTUATIONS,
MIAMI, FLORIDA**

by
Frederick W. Meyer
U. S. Geological Survey

REF

Prepared by the
UNITED STATES GEOLOGICAL SURVEY
in cooperation with the
BUREAU OF GEOLOGY
FLORIDA DEPARTMENT OF NATURAL RESOURCES
and with other
CITY, COUNTY, STATE, AND FEDERAL AGENCIES

Tallahassee, Florida

1974

CONTENTS

	Page
Abstract	1
Introduction	1
Purpose and scope	2
Methods of investigation	3
Acknowledgments	3
Location and geohydrologic setting	4
Water-level fluctuations in the Boulder Zone	8
Long-term fluctuations	9
Altitude of the water level	12
Atmospheric effects	13
Short-term fluctuations	15
Atmospheric tide	15
Earth and ocean tides	16
Water-level fluctuations in the upper part of the Floridan aquifer	20
Hydraulic characteristics of the Boulder Zone	21
Relation between aquifer characteristics and short-term water-level fluctuations	21
Hydraulic diffusivity	22
Specific storage and hydraulic conductivity	23
Transmissivity and storage coefficient	27
Summary and conclusions	28
References	31

LOCATION AND GEOHYDROLOGIC SETTING

The Peninsula well is in Dade County, about 10 miles southwest of Miami (fig. 1). It is 2,927 feet deep and is cased to 1,810 feet (fig. 2). The land surface at the well is about 6 feet above msl (National Ocean Survey, mean sea-level datum 1929).

The local water supply is obtained from the Biscayne aquifer, a highly permeable limestone strata that underlies the area to a depth of about 100 feet. Beneath the Biscayne aquifer is a 300-foot thick confining bed composed of sand and clay, which confines the water in the underlying Floridan aquifer system. The Floridan is about 1,500 feet thick and is composed of several




Figure 1 Map showing site location.

hydraulically separate water-bearing zones (Meyer, 1971). The upper 600-foot section is composed of limestone interbedded with calcareous clay and the lower 900-foot section (the principal water-bearing zone) is composed chiefly of highly permeable dolomitic limestone. The head and the salinity of the ground water increase with depth in the Floridan aquifer. Locally the head of the brackish water in the principal artesian water-bearing zone stands 41 feet above msl.





Figure 2 Sketch showing well construction.

**SUMMARY OF THE HYDROLOGY OF THE
FLORIDAN AQUIFER SYSTEM IN
FLORIDA AND IN PARTS OF GEORGIA,
SOUTH CAROLINA, AND ALABAMA**



REF

TABLE 1.—Terminology applied to the Floridan aquifer system

SERIES/STAGE		PARKER AND OTHERS (1955)		SPRINGFIELD (1966)		MILLER (1962b, 1962d)		MILLER (1986)	
		Formations ¹	Aquifer	Formations ¹	Aquifer	Formations ¹	Aquifers	Formations ¹	Aquifers
MIOCENE		Hawthorn Formation	Where permeable	Hawthorn Formation	Principal artesian aquifer	Hawthorn	Where permeable	Hawthorn	Where permeable
		Tampa Limestone		Tampa Limestone		Tampa Limestone		Tampa Limestone	
OLIGOCENE		Suwannee Limestone	Floridan aquifer	Suwannee Limestone	Principal artesian aquifer	Suwannee Limestone	Tertiary limestone aquifer system	Suwannee Limestone	Floridan aquifer system
EOCENE	Upper	Ocala Limestone		Ocala Limestone		Ocala Limestone		Ocala Limestone	
	Middle	Avon Park Limestone Lake City Limestone		Avon Park Limestone Lake City Limestone		Avon Park Limestone Lake City Limestone		Avon Park Formation	
	Lower			Oldamar Limestone		Oldamar Limestone		Oldamar Formation	
PALEOCENE						Cedar Keys Limestone		Cedar Keys Formation	

¹ Names apply only to peninsular Florida and southeast Georgia except for Ocala Limestone and Hawthorn Formation.

greater than that of those rocks that bound the system above and below. As shown in table 1, the Floridan includes units of Late Paleocene to Early Miocene age. Locally in southeast Georgia, the Floridan includes carbonate rocks of Late Cretaceous age (not shown in table 1). Professional Paper 1403-B presents a detailed geologic description of the Floridan, its component aquifers and confining units, and their relation to stratigraphic units.

The top of the Floridan aquifer system represents the top of highly permeable carbonate rock that is overlain by low-permeability material—either clastic or carbonate rocks. Throughout much of the area, this upper confining unit consists largely of argillaceous material of the Miocene Hawthorn Formation (table 1). Similarly the base of the Floridan is that level below which there is no high-permeability rock. Generally the underlying low-permeability rocks are either fine-grained clastic materials or bedded anhydrite. These sharp permeability contrasts at the top and base of the Floridan commonly occur within a formation or a time-stratigraphic unit as described by Miller (1986).

AQUIFERS AND CONFINING UNITS

The Floridan aquifer system generally consists of an Upper Floridan aquifer and a Lower Floridan aquifer, separated by less-permeable beds of highly variable properties termed the middle confining unit (Miller,

1986, p. B53). In parts of north Florida and southwest Georgia, there is little permeability contrast within the aquifer system. Thus in these areas the Floridan is effectively one continuous aquifer. The upper and lower aquifers are defined on the basis of permeability, and their boundaries locally do not coincide with those of either time-stratigraphic or rock-stratigraphic units. The relations among the various aquifers and confining units and the stratigraphic units that form them are shown on plate 1, a fence diagram modified from Miller (1986, pl. 30). A series of structure contour maps and isopach maps for the aquifers as well as the seven principal stratigraphic units that make up the Floridan aquifer system and its contiguous confining units is presented in Professional Paper 1403-B. These maps and associated cross sections were prepared by Miller (1986) based on geophysical logs, lithologic descriptions of cores and cuttings, and faunal data for the stratigraphic units, plus hydraulic-head and aquifer-test data for the hydrogeologic units.

The fence diagram shows the Floridan gradually thickening from a featheredge at the outcrop area of Alabama-Georgia-South Carolina to more than 3,000 ft in southwest Florida. Its maximum thickness is about 3,500 ft in the Manatee-Sarasota County area of southwest Florida. In and directly down dip from much of the outcrop area, the Floridan consists of only one permeable unit. Further down dip in coastal Georgia and

Summary of the Hydrology of the Floridan Aquifer System in Florida and in Parts of Georgia, South Carolina, and Alabama

By RICHARD H. JOHNSTON *and* PETER W. BUSH

R E G I O N A L A Q U I F E R - S Y S T E M A N A L Y S I S

U.S. GEOLOGICAL SURVEY PROFESSIONAL PAPER 1403-A

PROPERTY OF EPA
FIT IV

CONTENTS

	Page		Page
Abstract	A1	Hydraulic properties of the aquifer system	A9
Introduction	1	Transmissivity	9
Regional analysis of the Floridan aquifer system	2	Storage coefficient	12
Background, major objectives, and approach	2	Leakage coefficient	12
Purpose and scope of Professional Papers 1403-A through 1403-I	3	The regional flow system	13
Summary of previous work	4	Major features	13
Hydrogeology	5	Comparison of predevelopment and current conditions	14
Geologic setting	5	Ground-water development	16
Floridan aquifer system	6	Ground-water chemistry	18
Definitions and hydrogeologic terminology	6	Dissolved solids and major constituents	18
Aquifers and confining units	7	Hydrochemical facies	20
		Potential for future development	22
		Selected references	22

ILLUSTRATIONS

(Plates are in pocket)

- PLATE 1. Generalized fence diagram showing relation of geologic units to aquifers and confining units of the Floridan aquifer system.
- 2-4. Maps showing:
2. Occurrence of unconfined, semiconfined, and confined conditions and potentiometric surface (1980) of the Upper Floridan aquifer.
 3. Hydrochemical facies in the Upper Floridan aquifer.
 4. Potential areas for future development of large ground-water supplies from the Upper Floridan aquifer.

FIGURES		Page
1-5.	Maps showing:	
1.	Extent of the Floridan aquifer system, showing subareas whose hydrology is discussed in Professional Papers 1403-D through 1403-H	A4
2.	Transmissivity of the Upper Floridan aquifer	11
3.	Estimated predevelopment discharge from major ground-water areas of the Upper Floridan aquifer	15
4.	Estimated current (early 1980's) discharge from major ground-water areas of the Upper Floridan aquifer	17
5.	Estimated pumpage from the Floridan aquifer system by county, 1980	18
6.	Comparison of uses for ground water withdrawn from the Floridan aquifer system, 1960 and 1980	19
7.	Map showing dissolved-solids concentration of water from the Upper Floridan aquifer	20

TABLES

TABLE		Page
1.	Terminology applied to the Floridan aquifer system	A7
2.	Aquifers and confining units of the Floridan aquifer system	9
3.	Transmissivity and hydrogeologic conditions of the Upper Floridan aquifer and the upper confining unit in various localities	10

much of Florida, the Upper and Lower Floridan aquifers become prominent hydrogeologic units where they are separated by less-permeable rocks.

Overlying much of the Floridan aquifer system are low-permeability clastic rocks that are termed the upper confining unit. The lithology, thickness, and integrity of this confining unit has a controlling effect on the development of permeability in the Upper Floridan and the ground-water flow in the Floridan locally. (See later sections on transmissivity and regional ground-water flow.)

Plate 2 shows where the Upper Floridan is unconfined, semiconfined, or confined. Actually the Upper Floridan rarely crops out, and there is generally either a thin surficial sand aquifer or clayey residuum overlying the Upper Floridan. Sinkholes are common in the unconfined and semiconfined areas and provide hydraulic connection between the land surface and the Upper Floridan. In the semiconfined and confined areas, the upper confining unit is mostly the middle Miocene Hawthorn Formation, which consists of interbedded sand and clay that are locally phosphatic and contain carbonate beds. In southwest Florida, the carbonate beds locally form aquifers. Professional Papers 1403-E and 1403-F discuss these local aquifers in detail.

There are two important surficial aquifers overlying the upper confining unit locally: (1) the fluvial sand-and-gravel aquifer in the westernmost Florida panhandle and adjacent Alabama and (2) the very productive Biscayne aquifer (limestone and sandy limestone) of southeast peninsular Florida. Both of these aquifers occur in areas where water in the Floridan is saline; hence they are important sources of freshwater.

The Upper Floridan aquifer forms one of the world's great sources of ground water. This highly permeable unit consists principally of three carbonate units: the Suwannee Limestone (Oligocene), the Ocala Limestone (upper Eocene), and the upper part of the Avon Park Formation (middle Eocene). Detailed local descriptions of the geology and hydraulic properties of the Upper Floridan are provided in many reports listed in the references and especially in the summary by Stringfield (1966). The hydraulic properties section of this report discusses the large variation in transmissivity (as many as three orders of magnitude) within the Upper Floridan. Professional Paper 1403-B discusses the geologic reasons for these variations.

Within the Upper Floridan aquifer (and the Lower Floridan where investigated) there are commonly a few highly permeable zones separated by carbonate rock whose permeability may be slightly less or much less than that of the high-permeability zones. Many local studies of the Floridan have documented these

permeability contrasts, generally by use of current-meter traverses in uncased wells. For example, Wait and Gregg (1973) observed that wells tapping the Upper Floridan in the Brunswick, Ga., area obtained about 70 percent of their water from (approximately) the upper 100 ft of the Ocala Limestone and about 30 percent from a zone near the base of the Ocala. Separating the two zones is about 200 ft of less-permeable carbonate rock. Leve (1966) described permeable zones of soft limestone and dolomite and less-permeable zones of hard massive dolomite in the Upper Floridan of northeast Florida.

The Upper and Lower Floridan aquifers are separated by a sequence of low-permeability carbonate rock of mostly middle Eocene age. This sequence, termed the middle confining unit, varies greatly in lithology, ranging from dense gypsiferous limestone in south-central Georgia to soft chalky limestone in the coastal strip from South Carolina to the Florida Keys. Seven sub-regional units have been identified and mapped as part of the middle confining unit (see detailed descriptions in Professional Paper 1403-B). Much of the middle confining unit consists of rock formerly termed Lake City Limestone but referred to here as the lower part of the Avon Park Formation (table 1).

The Lower Floridan aquifer is comparatively less known geologically and hydraulically than the Upper Floridan. Much of the Lower Floridan contains saline water. For this reason and because the Upper Floridan is so productive, there is little incentive to drill into the deeper Lower Floridan in most areas. The Lower Floridan consists largely of middle Eocene to Upper Paleocene carbonate beds, but locally in southeast Georgia also includes uppermost Cretaceous carbonate beds. There are two important permeable units within the Lower Floridan: (1) a cavernous unit of extremely high permeability in south Florida known as the Boulder zone and (2) a partly cavernous permeable unit in northeast Florida and southeast coastal Georgia herein termed the Fernandina permeable zone. These units are further described in Professional Papers 1403-G and 1403-D, respectively.

Table 2 summarizes the geographic occurrence of aquifers and confining units within the Floridan aquifer system and shows the hydrogeologic nomenclature used in each Professional Paper. The units given in the table are hydraulic equivalents intended for use in describing and simulating the regional flow system. No stratigraphic equivalency or thickness connotation is intended in this table. For example, the Upper Floridan aquifer in the western Florida panhandle consists principally of the Suwannee (Oligocene) Formation. However, in central Florida the Ocala and Avon Park Formations constitute much of the high-permeability rock in the Upper Floridan.

Working Copy

Reference 15


NUS CORPORATION

INTERNAL CORRESPONDENCE

C-586-3-0-209

TO: K. D. Pass, Florida Section Leader

DATE: March 22, 1990

FROM: W. Smitherman 

COPIES: Phil Blackwell
Bob Donaghue
Katharine Siders

SUBJECT: Municipal Water Systems for Broward County, Florida

Due to the large number of sites in Broward County to be assessed, I have assembled a data base for the municipal water systems in the county. Information was obtained during visits to the municipalities, telephone conversations and through the mail. Two basic documents were generated, the first being the data base (attached as Appendix A) to provide the system names, a principal contact to verify information, telephone numbers, addresses, the number of connections or population served, number of wells and wellfields and a remarks section. The second document is a detailed topographic map showing the extent of the municipalities' distribution system along with the location of their wells and wellfields. In addition to the topographic map, almost all the municipalities provided maps, showing their distribution areas along with the wells and wellfields, for additional reference if needed.

The topographic map will be available in a central location so that the project managers can locate their sites on the map. The project managers can then identify the systems (wellfields) within the 4-mile radius of their sites and use the data base to call up only those municipalities within the 4-mile radius that pertain to their sites.

In preparing this information, several interesting items were identified:

1. The city of Ft. Lauderdale provides potable water to the cities of Wilton Manor and Oakland Park, since they do not have wells.
2. The city of Coconut Creek purchases water from the Broward County Utility Dept. (BCUD)-2A wellfield. Coconut Creek does not have municipal wells.
3. The city of Coral Springs has 4 different systems within the city limits. Coral Springs Improvement District provides potable water to the southern third of the city. The city of Coral Springs provides water to the middle third of the city. Royal Utilities (a small area) and the North Springs Improvement District provides potable water to the northern third of the city.
4. Broward County Utility Department (BCUD) has 7 systems in the county; however, system BCUD 3C is off-line and potable water is provided by the city of Hollywood.
5. All systems in the county have emergency hook-ups with other municipalities, except the Royal Utilities in Coral Springs. This system has no emergency hook-up.
6. Several communities have multiple wellfields; in all cases the water is mixed in the distribution lines. The three systems for the city of Plantation are presented since the number of connections for each were available.

7. The depths of wells were not recorded on the data base, since all the wells are obtaining water from the Biscayne aquifer, a sole-source aquifer. However, information obtained during interviews revealed that most municipal wells ranged from 80-120 feet below land surface (bls).
8. In general, the distribution area for each municipality was normally the corporate city limits.

The objective of this memorandum was to gather the needed information into one source and to assist the project manager in obtaining the groundwater use data necessary to complete the site assessments in a timely manner. Bringing together all the municipal systems in the county into one data base and one map showing the locations should expedite this process. Any project managers wishing to access the data base should consult either you or me.

✓ = Distribution system on file at FIT

MUNICIPAL WATER SYSTEM
FOR BROWARD COUNTY, FL

03/28/90

SYSTEM	CONTACT PHONE	ADDRESS	(P)OP SERVED (C)ONNECTIONS	# OF WELLS	# OF FIELDS	DATE ENTERED	REMARKS
✓ BCUD - 1A	MIKE SCOTTIE (305)960-3051	BROWARD CTY UTIL DPT 2401 N POWERLINE RD POMPANO BEACH, FL 33064	10843 (C)	7	1	03/19/90	Emergency hookups with Ft. Lauderdale, Tamarac, and Lauderdale
✓ BCUD - 1B	MIKE SCOTTIE (305)960-3051	BROWARD CTY UTIL DPT 2401 N POWERLINE RD POMPANO BEACH, FL 33064	3397 (C)	5	1	03/15/90	In production 8 hrs/day, interconnect with BCUD-1A Emergency hookup with Ft. Lauderdale
██████████	MIKE SCOTTIE (305)960-3051	BROWARD CTY UTIL DPT 2401 N POWERLINE RD POMPANO BEACH, FL 33064	██████████			03/15/90	Emergency hookups with Deerfield Beach
✓ BCUD - 3A	MIKE SCOTTIE (305)960-3051	BROWARD CTY UTIL DPT 2401 N POWERLINE RD POMPANO BEACH, FL 33064	5305 (C)	6	1	03/15/90	Emergency hookups with Dania, Ft. Lauderdale
✓ BCUD - 3B	MIKE SCOTTIE (305)960-3051	BROWARD CTY UTIL DPT 2401 N POWERLINE RD POMPANO BEACH, FL 33064	6207 (C)	4	1	03/15/90	Emergency hookups with Miramar and Hollywood
✓ BCUD - 3C	MIKE SCOTTIE (305)960-3051	BROWARD CTY UTIL DPT 2401 N POWERLINE RD POMPANO BEACH, FL 33064	3648 (C)	3	1	03/15/90	System OFF-LINE; Purchas- ing water from City of Hollywood
✓ BROADVIEW	MIKE SCOTTIE (305)960-3051	BROWARD CTY UTIL DPT 2401 N POWERLINE RD POMPANO BEACH, FL 33064	2185 (C)	3	1	03/15/90	Emergency hookups with Tamarac and N. Lauderdale
✓ BROADVIEW PARK W.D.	MIKE SCHWAB (305)583-4223	BROADVIEW PARK W.D. 1955 SW 50TH AVE PLANTATION, FL 33317	1800 (C)	1	1	03/19/90	Emergency hookups with Plantation
██████████	GARTH HINCKEL (305)973-6784	COCONUT CK WATER DPT 4800 W COPAND RD COCONUT CREEK, FL 33063	██████████			03/19/90	Potable water supplied by BCUD - 2A
COOPER CITY * Making out 3/28/90	GEORGE HACKNEY (305)434-5519	COOPER CITY UTIL 90 SW 50TH PLACE COOPER CITY, FL 33328	7500 (C)	6	2	03/15/90	Emergency hookups with Dania and Bonaventure

MUNICIPAL WATER SYSTEM
FOR BROWARD COUNTY, FL

03/28/90

SYSTEM	CONTACT PHONE	ADDRESS	(P)OP SERVED (C)ONNECTIONS	# OF WELLS	# OF FIELDS	DATE ENTERED	REMARKS
✓ CORAL SPRGS IMPRM DS	CHUCK PERRON (305)753-0380	CORAL SPRGS IMPRM DS 10300 NW 11TH MANOR CORAL SPRINGS, FL 33071	30000 (P)	7	1	03/19/90	Emergency hookups with Coral Springs
✓ CORAL SPRINGS	AL PAZIN (305)344-1172	CITY OF CORAL SPRING 9551 W SAMPLE RD CORAL SPRINGS, FL 33075	40000 (P)	12	1	03/19/90	Emergency hookups with Coral Springs and North Springs Improvement Dist
✓ DANIA	DON WINDHAM (305)921-7781	BERRY AND CALVIN INC 2 OAKWOOD BLVD ST120 HOLLYWOOD, FL 33020	4064 (C)	2	1	03/15/90	Additional potable water provided by BCUD, Ft. Lauderdale and Hollywood
✓ DAVIE	DANIEL COLABELLA (305)797-1080	DAVIE WATER SYSTEM 6591 SW 45TH ST DAVIE, FL 33314	7000 (C)	16	2	03/19/90	Emergency hookups with Hollywood, Cooper City and Ft. Lauderdale
✓ DEERFIELD BEACH	DALE HOLINBECK (305)480-4270	CITY OF DEERFIELD BC 150 NE 2ND AVE. DEERFIELD, FL 33441	10800 (C)	18	2	03/15/90	Emergency hookups with BCUD 2A, Hillsboro Bch and Boca Raton
✓ FERNCREST UTILITIES	ROBERT SALERNO (305)989-6200	FERNCREST UTILITIES 3015 SW 54TH AVE. FT. LAUDERDALE, FL 33314	1600 (C)	2	1	03/15/90	Emergency hookups with Davie and Ft. Lauderdale
✓ FT LAUDERDALE	JAMES SINDELAR (305)492-7858	FT LAUDERDALE UTIL P.O. BOX 14250 FT. LAUDERDALE, FL 33302	56000 (C)	43	2	03/15/90	Supply potable water to Wilton Manor, Oakland Park, BCUD, BC Port Auth, Dania and Tamarac East
✓ HILLSBORO BEACH	RODNEY MAIN (305)941-8937	HILLSBORO BCH WATER 925 NE SAMPLE RD POMPANO BEACH, FL 33064	185 (C)	3	1	03/15/90	Emergency hookups with BCUD 2A, Deerfield Beach, Seasonal pop from 2300 - 3800
✓ HOLLANDALE	MIKE GOOD (305)458-3251	DEPT OF PUBLIC WORKS 308 S DIXIE HWY HOLLANDALE, FL 33009	5500 (C)	2	1	03/15/90	6 wells shut down, salt- water intrusion. Addi- tional water supplied by N. Miami
✓ HOLLYWOOD	MARSHALL BERGAKER (305)921-3251	CITY OF HOLLYWOOD UT P.O. BOX 229045 HOLLYWOOD, FL 33022	130000 (P)	20	2	03/28/90	Supplies potable water to Dania. Emergency hookups with surrounding munici- palities

MUNICIPAL WATER SYSTEM
FOR BROWARD COUNTY, FL

03/28/90

SYSTEM	CONTACT PHONE	ADDRESS	(P)OP SERVED (C)ONNECTIONS	# OF WELLS	# OF FIELDS	DATE ENTERED	REMARKS
* LAUDERHILL <i>Sending copy 3/26/90</i>	JOHN SCHRIEFFER (305)739-0100	CITY OF LAUDERHILL 2000 CITY HALL DRIVE LAUDERHILL, FL 33313	8600 (C)	7	1	03/21/90	Emergency hookups with Plantation and Sunrise
✓ MARGATE	RICK VAN ACKER (305)972-0828	MARGATE UTILITIES 1001 W RIVER DR MARGATE, FL 33063	23723 (C)	12	2	03/19/90	Emergency hookups with N. Lauderdale and Pompano Beach
✓ MIRAMAR	LOU BADAMI (305)989-6200	MIRAMAR CITY HALL 6740 MIRAMAR PKWY MIRAMAR, FL 33083	12100 (C)	9	2	03/15/90	Emergency hookups with BCUD 3C and Pembroke Pine
✓ NORTH LAUDERDALE	ED GOEBELS (305)722-0900	CITY OF N LAUDERDALE 701 SW 71ST AVE NORTH LAUDERDALE, FL 33068	6328 (C)	3	1	03/19/90	Emergency hookups with Tamarac, BCUD, and Margate
✓ NORTH SPRGS IMPRM DS	CHUCK PERRON (306)753-0380	NORTH SPRGS IMPRM DS 10300 NW 11TH MANOR CORAL SPRINGS, FL 33071	5000 (P)	2	1	03/19/90	Emergency hookups with Coral Springs. Two (2) new wells due 6/90
✓ OAKLAND PARK	ROLLAND SALSBERY (305)561-6259	OAKLAND PARK UTIL 3650 NE 12TH AVE OAKLAND PARK, FL 3334	2700 (C)	0	0	03/15/90	Potable water supplied by City of Ft. Lauderdale
PEMBROKE PINES	DAVE MARTINEZ (305)435-6540	CITY OF PEMBROKE PNS 7960 JOHNSON ST PEMBROKE PINES, FL 33024	31581 (C)	8	2	03/15/90	Emergency hookups with Cooper City, Hollywood and Miramar
* PLANTATION CENTRAL	DUAINE WALLACE (305)797-2169	CITY OF PLANTATION 700 NW 91ST AVE PLANTATION, FL 33317	10043 (C)	10	1	03/23/90	Interconnected with Plantation East System
* PLANTATION EAST	DUAINE WALLACE (305)797-2169	CITY OF PLANTATION 500 NW 65TH AVE PLANTATION, FL 33317	9891 (C)	10	1	03/28/90	Emergency hookups with Ft. Lauderdale, Sunrise and Broward Park. Inter- connected with Pltn Cntrl
* PLANTATION WEST <i>Sending topo map 3/28/90</i>	DUAINE WALLACE (305)797-2169	CITY OF PLANTATION 700 NW 91ST AVE PLANTATION, FL 33317	1336 (C)	0	0	03/23/90	Potable water supplied by Plantation Central

MUNICIPAL WATER SYSTEM
FOR BROWARD COUNTY, FL

03/28/90

SYSTEM	CONTACT PHONE	ADDRESS	(P)OP SERVED (C)ONNECTIONS	# OF WELLS	# OF FIELDS	DATE ENTERED	REMARKS
✓ POMPANO BEACH	STAN LEMCKE (305)786-4105	POMPANO BCH PBLC WKS P.O.BOX 1300 POMPANO BEACH, FL 33061	16900 (C)	22	2	03/19/90	Emergency hookups with BCUD - 2A
ROYAL UTILITY <i>Will call back. 3/28/90pm to discuss</i>	DOUGLAS BRIGHT (305)341-7565	ROYAL UTILITY CO 8900 NW 44TH COURT CORAL SPRINGS, FL 33065	173 (C)	3	1	03/19/90	No Emergency hookups
✓ SUNRISE	WALTER GERRARD (305)741-6570	CITY OF SUNRISE 4350 SPRINGTREE DR SUNRISE, FL 33351	29742 (C)	28	3	03/22/90	Emergency hookups with Plantation and Lauderhill
✓ TAMARAC	LONNIE SCOTT (305)726-2300	TAMARAC UTILITIES 7805 NW 61ST ST TAMARAC, FL 33321	17074 (C)	13	1	03/19/90	Emergency hookups with BCUD -1A and Lauderhill
✓ WILTON MANOR	JOE MOSS (305)390-2190	CITY OF WILTON MANOR 524 NE 21ST COURT WILTON MANOR, FL 33305	4500 (C)	0	0	03/15/90	Potable water supplied by city of Ft. Lauderdale

THURSDAY, APRIL 26, 1990, THE MIAMI HERALD

Road plan saves tortoise habitat

By **CURTIS MORGAN**
Herald Staff Writer

A yearlong debate over a Fort Lauderdale Executive Airport road that threatened a gopher tortoise haven all but ended Wednesday in a compromise as rare as the creature itself.

The solution pleased all sides — environmentalists and business people.

An access road that would have skirted the border of a 15.2-acre ridge of white sand covered with rare rosemary scrub providing a home to lizards, rodents and turtles can be rerouted, airport manager William Crouch Jr. told the Broward County Urban Wilderness Advisory Board on Wednesday night.

Elated board members, who had argued that the original road would have chewed up dunes and grasses that nourish the preserve's

PLEASE SEE GOPHER, 88R

TURTLE TIDBITS

The gopher tortoise is a land turtle that can live to be 40 years old and grow as long as 14 inches. It is classified by Florida as a "species of special concern." It lives in deep underground sand burrows, which house three dozen species of animals, including the rare Florida gopher frog, the Florida mouse, the threatened Eastern indigo snake, the Florida pine snake and three kinds of beetles.

Other rare species on the site:

- The Florida scrub lizard, a rare reptile with iridescent blue belly scales.
- The large-flowered rosemary, a member of the mint family.
- Curtiss' milkweed, a threatened flowering perennial with leaves that resemble oak leaves.
- Bromeliads, scrub palmetto, spike moss and a variety of lichens.

Compromise road plan saves habitat of turtles

GOPHER, FROM 18R

turtles, endorsed the design.

"You're talking about the environmental community and government and the private sector getting together to work out a solution," said David Utley, the board's vice chairman.

Airport authorities want the road to lead from Cypress Creek Road to an operations center, cargo gates and U.S. Customs Service office that will be built on the airport's north side. It also would improve access for emergency vehicles.

The road would have run about

600 feet north of the east-west runway, behind the Allied Signal Aerospace complex parallel to Cypress Creek Road. Under the original design, a section would have reached 50 feet into the preserve.

In May, over environmentalists' objections, the Fort Lauderdale City Commission approved the route but asked airport officials to continue to seek a compromise.

It came when Allied Signal agreed to allow the road to be built farther east in six acres it plans to develop. City engineers and airport staffers drew up a new design that actually will expand the turtle territory.

HP

REGION: 04
STATE: FL

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 1
RUN DATE: 02/24/86
RUN TIME: 09:07:13

M.2 - SITE MAINTENANCE FORM

EPA ID : FLD981026933		* ACTION: _	*
SITE NAME: ACME PLASTICS	SOURCE: R	* _____	*
STREET : 750 NW 57 CT.	CONG DIST: 12	* _____	*
CITY : FT. LAUDERDALE	ZIP: 33309	* _____	*
CNTY NAME: BROWARD	CNTY CODE : 011	* _____	*
LATITUDE : 26/11/36.0	LONGITUDE : 080/10/54.0	* _/_/_._	*
LE-SOURCE: G	LL-ACCURACY:	* _	*
SMSA : 2680	HYDRO UNIT: 03090202	* _____	*
INVENTORY IND: Y	REMEDIAL IND: Y	REMOVAL IND: N	FED FAC IND: N
NPL IND: N	NPL LISTING DATE:	NPL DELISTING DATE:	
SITE/SPILL IDS:			
RPM NAME:	RPM PHONE: - -	* _____	*
SITE CLASSIFICATION:	SITE APPROACH:	* _	*
DIOXIN TIER:	REG FLD1:	REG FLD2:	
RESP TERM: PENDING ()	NO FURTHER ACTION ()	* PENDING ()	NO FURTHER ACTION ()
ENF DISP: NO VIABLE RESP PARTY ()	VOLUNTARY RESPONSE ()	* _	*
ENFORCED RESPONSE ()	COST RECOVERY ()	* _	*
SITE DESCRIPTION:		* _____	*
		* _____	*
		* _____	*
		* _____	*

REGION: 04
STATE : FL

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 2
RUN DATE: 02/24/86
RUN TIME: 09:07:13

M.2 - PROGRAM MAINTENANCE FORM

SITE: ACME PLASTICS

EPA ID: FLD981026933 PROGRAM CODE: H01 PROGRAM TYPE:

PROGRAM QUALIFIER: ALIAS LINK :

PROGRAM NAME: SITE EVALUATION

DESCRIPTION:

* ACTION: _

* _ *

* _ *

* _ *

* _ *

* _ *

REGION: 04
STATE : FL

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 3
RUN DATE: 02/24/86
RUN TIME: 09:07:18

M.2 - EVENT MAINTENANCE FORM

* ACTION: _

SITE: ACME PLASTICS
PROGRAM: SITE EVALUATION

EPA ID: FLD981026933 PROGRAM CODE: H01

EVENT TYPE: DS1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: S

EVENT NAME: DISCOVERY

STATUS:

DESCRIPTION:

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

ORIGINAL

CURRENT

ACTUAL

START:

START:

START:

* _/_/_ _/_/_ _/_/_ *

COMP :

COMP :

COMP : 06/01/85

* _/_/_ _/_/_ _/_/_ *

HQ COMMENT:

* _ _ _ _ _ *

* _ _ _ _ _ *

RG COMMENT:

COOP AGR #

AMENDMENT #

STATUS

STATE %

0

* _ _ _ _ _ *

REGION: 04
STATE : FL

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 4
RUN DATE: 02/24/86
RUN TIME: 09:07:13

M.2 - EVENT MAINTENANCE FORM

SITE: ACME PLASTICS
PROGRAM: SITE EVALUATION

EPA ID: FLD981026933 PROGRAM CODE: H01

EVENT TYPE: PA1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: S

EVENT NAME: PRELIMINARY ASSESSMENT

STATUS:

DESCRIPTION:

* ACTION: _

* _ _ _ _ _
* _ _ _ _ _
* _ _ _ _ _
* _ _ _ _ _
* _ _ _ _ _

ORIGINAL

CURRENT

ACTUAL

START:

START:

START: 01/21/86

* _/_/_ _/_/_ _/_/_ *

COMP :

COMP :

COMP : 02/10/86

* _/_/_ _/_/_ _/_/_ *

HQ COMMENT:

* _ _ _ _ _

RG COMMENT:

* _ _ _ _ _

COOP AGR #

AMENDMENT #

STATUS

STATE X

0

* _ _ _ _ _

REGION: 04
STATE : FL

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 5
RUN DATE: 02/24/86
RUN TIME: 09:07:13

M.2 - REGIONAL UTILITY MAINTENANCE FORM

SITE: ACME PLASTICS
EPA ID: FLD981026933

REG CODE: HSCS-01
DESCRIPTION: SOLVENTS (METHYL, ETHYL & KETONE)

DATE1:

DATE2:

DATE3:

FREE FIELD:

REG CODE: OPDU-01
DESCRIPTION: UNKNOWN DISPOSAL ON SITE

DATE1:

DATE2:

DATE3:

FREE FIELD:

REG CODE: 4C85-01
DESCRIPTION: CERCLA FY85 COOPERATIVE AGREEMENT

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

* _____

* _____

* _/_/_

* _/_/_

* _/_/_

* _____

* ACTION: _

* _____

* _____

* _/_/_

* _/_/_

* _/_/_

* _____

* ACTION: _

* _____

* _____

* _/_/_

* _/_/_

* _/_/_

* _____

REGION: 04
STATE : FL

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 6
RUN DATE: 02/24/86
RUN TIME: 09:07:13

M.2 - REGIONAL UTILITY MAINTENANCE FORM

SITE: ACME PLASTICS
EPA ID: FLD981026933

REG CODE: 4EWF-01
DESCRIPTION: EXECUTIVE WELL FIELD STUDY SITE

DATE1:

DATE2:

DATE3:

FREE FIELD:

REG CODE: 4HRN-01
DESCRIPTION: PRELIMINARY HRS NEEDED

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

* _____ *

* _____ *

* _/_/_/ _ *

* _/_/_/ _ *

* _/_/_/ _ *

* _____ *

* ACTION: _

* _____ *

* _____ *

* _/_/_/ _ *

* _/_/_/ _ *

* _/_/_/ _ *

* _____ *

)

ACME PLASTICS, INC.
FLD981026933
PRELIMINARY ASSESSMENT

F.T.E.W.

- A. SITE DESCRIPTION. Acme Plastics, Inc. was located in a commercial/ industrial area at 750 NW 57th CT, Fort Lauderdale, Broward County, Florida. The facility was a manufacturer of plastic letters for the sign industry from at least 1974 to 1982. The Foam Factory is now located at this site.
- B. DESCRIPTION OF HAZARDOUS CONDITIONS, INCIDENTS AND PERMIT VIOLATIONS. Acme Plastics, Inc. was a manufacturer of plastic letters for signs and the process involved injection molding. The plastics that were used were styrene, polypropylene and acrylics. Waste plastic was reused or baled for scrap resale. The injection molding presses required cooling water and hydraulic oil. Methyl ethyl ketone (MEK) was used during the manufacturing of the plastic until 1979. An industrial sludge survey, 5/19/81, stated that no waste is generated, and as of 3/18/82, the facility was given a non-source status. The Foam Factory is now located at this site, and there is no information available about this facility.
- Cooling water for the injection molding presses was obtained from a closed loop supply and discharge well system. Both supply and discharge wells are 4 inches in diameter and 150 feet deep, with a maximum continuous flow of 10,000 GPD. On 11/10/81 water samples were taken from the system just before the discharge well. The results indicated that the facility was in compliance with groundwater discharge standards. The current status of the supply/discharge wells is unknown. No permit violations have been reported.
- C. NATURE OF HAZARDOUS MATERIALS. The hazardous materials that were at the site were MEK which is volatile, reactive and flammable, styrene which is reactive and flammable, paint and oil.
- D. ROUTES OF CONTAMINATION. Possible routes of contamination include drinking water, surface water, soils and groundwater used for irrigation and other purposes.
- E. POSSIBLE AFFECTED POPULATION AND RESOURCES. Area residents are provided with drinking water from the City of Fort Lauderdale Executive/ Prospect municipal wellfield. The wellfield draws from the Biscayne aquifer, which is a shallow, permeable, sole-source aquifer. The site is located 2000 feet east of the nearest wells, thus, potential contaminants in the groundwater may reach the wellfield.
- F. RECOMMENDATIONS AND JUSTIFICATIONS. Acme Plastics, Inc. is no longer located at this site; the present site occupant is the Foam Factory. Acme Plastics was given a "non-source status" in March, 1982. There is no information available for the Foam Factory. A low priority for inspection is recommended at this facility; however, the status of the well system should be ascertained.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

IDENTIFICATION
01 STATE 02 SITE NUMBER
FL D981026932

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site)

Acme Plastics, Inc.

02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER

750 NW 57th CT

03 CITY

Fort Lauderdale

04 STATE

FL

05 ZIP CODE

33309

06 COUNTY

Broward

07 COUNTY CODE

011

08 COUNTY DIST

17

09 COORDINATES LATITUDE

26 12 15

LONGITUDE

080 08 57

10 DIRECTIONS TO SITE (Starting from nearest public road)

Proceed north on I-95 from Fort Lauderdale, exit onto Commercial Blvd; proceed west on Commercial Blvd. 1/4 mile to Powerline Rd.; proceed north on Powerline 3000 feet to NW 57th CT.; proceed east on NW 57th CT, the site is the last building on the left.

III. RESPONSIBLE PARTIES

01 OWNER (if known)

Acme Plastics, Inc.

02 STREET (Business, mailing, residential)

750 NW 57th CT

03 CITY

Fort Lauderdale

04 STATE

FL

05 ZIP CODE

33309

06 TELEPHONE NUMBER

(305) 772-3720

07 OPERATOR (if known and different from owner)

Frank Nickola - General Manager

08 STREET (Business, mailing, residential)

Same

09 CITY

Fort Lauderdale

10 STATE

FL

11 ZIP CODE

33309

12 TELEPHONE NUMBER

()

13 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE ☐ B. FEDERAL:

(Agency name)

☐ C. STATE

☐ D. COUNTY

☐ E. MUNICIPAL

☐ F. OTHER:

(Specify)

☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check at least one)

☐ A. RCRA 3001 DATE RECEIVED:

MONTH DAY YEAR

☐ B. UNCONTROLLED WASTE SITE (RCRA 109(c)) DATE RECEIVED:

MONTH DAY YEAR

☒ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION

☒ YES

DATE

MONTH DAY YEAR

☐ NO

BY (Check all that apply)

☐ A. EPA

☐ B. EPA CONTRACTOR

☐ C. STATE

☐ D. OTHER CONTRACTOR

☐ E. LOCAL HEALTH OFFICIAL

☒ F. OTHER: Broward County Environmental

CONTRACTOR NAME(S): Quality Control Board (BCEQCB)

02 SITE STATUS (Check one)

☐ A. ACTIVE

☒ B. INACTIVE

☐ C. UNKNOWN

03 YEARS OF OPERATION

Pre-1974

1982

☒ UNKNOWN

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Acme Plastics was a manufacturer of plastic letters for the sign industry. Methyl ethyl ketone, paint, styrene and oil were used in the manufacturing process.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

Methyl ethyl ketone (MEK) was used in the plastics manufacturing process. It is not known how much spent MEK was generated or the method of disposal. Rinsewater was discharged and drained into a storm sewer near the building in 1975.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents)

☐ A. HIGH

(Inspection required promptly)

☐ B. MEDIUM

(Inspection required)

☒ C. LOW

(Inspect on time available basis)

☐ D. NONE

(No further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT

Eric Nuzie *Contract 3. 1988*

02 OF (Agency/Organization)

FDER

03 TELEPHONE NUMBER

904 1488-0190

04 PERSON RESPONSIBLE FOR ASSESSMENT

Willard Murray

05 AGENCY

N/A

06 ORGANIZATION

E.C. Jordan Co.

07 TELEPHONE NUMBER

207 775-5401

08 DATE

11 / 7 / 85



☒ I. HIGHLY VOLATILE
☐ J. EXPLOSIVE
☒ K. REACTIVE
☐ L. INCOMPATIBLE
☐ M. NOT APPLICABLE

EPA 551 10-12-17-011



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1. IDENTIFICATION	
01 STATE	02 SITE NUMBER
FL	D981026911

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

Rinsing of painted silk screens was done on-site in 1975, the rinsewater mixed with some paint waste and cleaner drained into the back alley to a storm sewer. Contaminants in this rinsewater may have contaminated the groundwater. No groundwater samples have been taken.

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

The site is less than 1 mile south of Cypress Creek Canal. Potential contaminants in the groundwater may have reached nearby surface water. No surface water samples have been taken.

01 ☒ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 0 04 NARRATIVE DESCRIPTION

No file information is available regarding the present site occupant.

01 ☒ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 0 04 NARRATIVE DESCRIPTION

No file information is available regarding the present site occupant.

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 0 04 NARRATIVE DESCRIPTION

No file information is available regarding the present site occupant.

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: <0.5 04 NARRATIVE DESCRIPTION
(Acres)

Possible spills of materials on-site or discharged rinsewater may have contaminated soil on-site. No soil samples have been taken.

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

Area residents are provided with drinking water from the Fort Lauderdale Executive/Prospect Municipal Wellfield which produces from the shallow and permeable Biscayne aquifer. The site is located 2000 feet east of the nearest wells, and contaminants in the groundwater, may reach the Wellfield.

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: 0 04 NARRATIVE DESCRIPTION

Remote potential. The ACME facility is no longer active, thus, causing no potential for worker injury. However, no information is available for the current site occupant.

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 10,000+ 04 NARRATIVE DESCRIPTION

Area residents may be exposed to hazardous substances via groundwater used for irrigation and other purposes, surface water, drinking water and soils.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
FL D981026933

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☒ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED

Contact with contaminants may damage plant life. There have been no reports of damage to the grass and trees on-site.

01 ☒ K. DAMAGE TO FAUNA

04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED

Contact with contaminants may injure wildlife. However, the site is located in a highly populated commercial/industrial area largely devoid of wildlife.

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

Remote potential. The solvents that were used on-site do not generally bio-accumulate.

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES

(Spills/runoffs/leaking drums/leaking drums)

03 POPULATION POTENTIALLY AFFECTED: 0

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

04 NARRATIVE DESCRIPTION

None reported.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

None reported.

01 ☒ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED

Rinsewater was discharged into an alley and drained into a storm sewer in 1975.

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

None reported.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

None known.

III. TOTAL POPULATION POTENTIALLY AFFECTED: 10,000+

IV. COMMENTS


The facility was active from at least 1974 to 1982. Cooling water was obtained through a closed loop supply and discharge well system; current status of this well system is unknown. The site was declared a non-source status, 3/18/85.

V. SOURCES OF INFORMATION (Check specific references, e.g., site files, sample analysis, reports)


See attached reference list.

ATTACHMENT A
ACME PLASTICS, INC.
FLD981026933
ON-SITE INSPECTIONS

<u>Date</u>	<u>Agency</u>	<u>Samples</u>	<u>Comments</u>
7/30/85	E.C. Jordan Co. for FDER	No	Windshield survey (off-site inspection) found that Acme Plastics was no longer at the site.
7/20/82	FDER	No	No problems noted.
11/10/81	FDER	Yes	Groundwater discharge analysis, no problems noted.
5/19/81	FDER	No	Industrial sludge survey.
9/20/74 to 5/14/80	FDER	No	(15) Inspection Reports.



SCALE 1 : 24000



SITE LOCATION MAP

Acme Plastic, Inc.

750 NW 57 Court

USGS QUAD Ft. Lauderdale North

DATE 1983

E.C. JORDAN CO.

REFERENCE LIST

1. Environmental Protection Agency, Federal Register, National Oil and Hazardous Substances Contingency Plan, Part V, July 16, 1982.
2. Farm Chemicals Handbook, Willoughby, OH; Meister Publishing Company, 1982.
3. Florida Department of Environmental Regulation, The Sites List, Summary Status Report, July 1, 1983 - June 30, 1984.
4. Florida Department of Environmental Regulation, 3012 Folder, 2600 Blairstone Road, Tallahassee, Florida. To be used for completion of Preliminary Assessment, Form 2070-12.
5. Florida Department of Natural Resources, Water Resources of Broward County, Report of Investigation No. 65, 1973.
6. Florida Division of Geology, Chemical Quality of Waters of Broward County, Florida, Report of Investigations No. 51, 1968.
7. Florida Geological Survey, Biscayne Aquifer of Dade and Broward Counties, Florida, Report of Investigation No. 17, 1958.
8. Florida Geological Survey, Groundwater Resources of the Oakland Park Area of Eastern Broward County, Florida, Report of Investigation No. 20, 1959.
9. Health and Safety Plan, Florida 3012 Program, E.C. Jordan Co., June 1984.
10. Healy, Henry G., 1977, Public Water Supplies of Selected Municipalities in Florida, 1975: U.S. Geological Survey, Water-Resources Investigations 77-53, p. 309.
11. NUS Project for Performance of Remedial Response Activities at Uncontrolled Hazardous Substance Facilities--Zone 1. NUS Corporation, Superfund Division.
12. NUS Training Manual, Project for Performance of Remedial Response Activities at Uncontrolled Hazardous Substance Facilities--Zone 1, NUS Corporation, Superfund Division.
13. Sax, N. Irving, Dangerous Properties of Industrial Materials, Sixth Edition, Van Nostrand Reinhold Co., 1984.
14. TLVs Threshold Limit Values for Chemical Substances in the Work Environment Adopted by ACGIH for 1983-84, American Conference of Governmental Industrial Hygienists, ISBN: 0-936712-45-7, 1983.
15. U.S. Geological Survey, Topographic Map, 1-24,000 Series.
16. Windholz, M., ed. The Merck Index, an Encyclopedia of Chemicals and Drugs, Rahway, NJ: Merck and Company, Inc., 1976.

OVERSIZED

DOCUMENT

MAP